

**SURVEY & REMONUMENTATION**

**FEB 17 1998**

**SECTION**

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**



**2630**  
Page: 1 of 1  
12/16/1997 12:15P

For Corners in  
**BARRY COUNTY**

Located In:

Corner

Sandy Schondelmayer - Barry Co. LCRCR

1. Public Land Survey T..4N R..8W .....K-10.....  
SEC. COR COMMON T..... R.....  
TO SEC'S 25 & 26 T..... R.....  
CARLTON TWP. T..... R.....

Register of Deeds Stamp & File Number

2. Property Controlling S..... T..... R.....  
in Section S..... T..... R.....

3. Miscellaneous S..... T..... R.....  
Property in Sec. S..... T..... R.....

4. Lot No....., Recorded Plat.....  
5. Private Claims.....

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, RAYMOND MOORED, in a field survey on MAY 8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
GLO: SYLVESTER SIBLEY D.S. 1830 (R8W, P. 144) A. BEECH 16. S. 66. W 15; BEECH 7 N. 52 1/2 E. 46 1/2.

NO OTHER CORNER HISTORY AVAILABLE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP MIDWAY AND ON LINE BETWEEN K-9 AND K-11.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 8 July '96 *BR*

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP  
-NAIL & TAG IN N SIDE 10" CHERRY N75E 23.50'  
-NAIL & TAG IN N SIDE 4" HICKORY N85E 22.44'  
-NAIL & TAG IN W SIDE 8" HICKORY N40E 38.72'  
-NAIL & TAG IN E SIDE 20" HICKORY N50W 44.04'

*Raymond Moored* Date 12/11/97  
Surveyor's Michigan License No. 26463

