

SURVEY & REMONUMENTATION

FEB 17 1998


SECTION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in BARRY COUNTY

Located In:

Corner Cc



2639 Page: 1 of 1 12/16/1997 12:15P

1. Public Land Survey SEC COR COMMON TO SEC'S 25, 26, 35, 36 CARLTON TWP.

T.4N R.8W ...K-11... T..... R..... T..... R..... T..... R.....

2. Property Controlling in Section

S..... T..... R..... S..... T..... R.....

3. Miscellaneous Property in Sec.

S..... T..... R..... S..... T..... R.....

4. Lot No....., Recorded Plat.....

5. Private Claims.....

Register of Deeds Stamp & File Number

Grid table with columns A-M and rows 1-13. A dot is marked at row 11, column J.

I, RAYMOND MOORED, in a field survey on MAY8, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: GLO: SYLVESTER SIBLEY D.S. 1830 (R8W, P. 143) A. BEECH 5. S. 36. W 24 1/2 ; BEECH. 8 N.13.E. 14. NO OTHER CORNER HISTORY AVAILABLE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND 1/2" REROD IN INTERSECTION OF ROADS. HOLDING THIS POSITION MATCHED REASONABLY WELL WITH 1/8 LINE OCCUPATIONS TO WEST AND NORTH. SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP AT THIS POSITION.

ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL REESTABLISHMENT OF THE POSITION OF THE ORIGINAL CORNER.

APPROVED BY BARRY COUNTY REMONUMENTATION PEER GROUP ON 8 July 96 [Signature]

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: SET STANDARD BARRY COUNTY REMONUMENTATION IRON WITH CAP -REF. IRON N45W 41.51' ( JUST OFF EDGE OF GRAVEL) -REF. IRON S50E 35.55' ( 8' OFF EDGE OF ROAD) -NAIL & TAG IN N SIDE 12" WALNUT S70W 109.33' -NAIL & TAG IN N SIDE 15" WALNUT S75W 131.15'

[Signature] Date: 12/11/97 Surveyor's Michigan License No. 26463

