

AUG 22 1995

COMMISSION

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

MAR 20 10 55 AM '95

Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schindelmarer REGISTER OF DEEDS

For corners in

BARRY

(County)

Located In:

Corner Code #

1. Public Land Survey N 1/4 CORNER SECTION 1 CARLTON TOWNSHIP ON TOWNSHIP LINE

T 4N R8W

L-1

2. Property Controlling in Section

S T R

3. Miscellaneous Property in Sec.

S T R

002298

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

Grid table with columns A-M and rows 2-13, containing numbers 1-36.

I, BRIAN REYNOLDS, in a field survey on 15 APRIL 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT SET BY GENERAL LAND OFFICE NO RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND L-13, T5N, R8W, IONIA COUNTY (PLOW POINT IN GRAVEL ROAD). MEASURED EAST TO MID-POINT BETWEEN K-1 AND M-1, POSITION FELL IN LINE WITH FENCE TO THE SOUTH. EXCAVATION BELOW GRAVEL ROAD REVEALED NOTHING. SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT ON LINE BETWEEN L-13 AND M-13 T5N, R8W, AND MID-DISTANCE BETWEEN K-1 AND M-1 T4N, R8W.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON 3 May '94 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP) SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A UTILITY POLE S01°W 107.38' SET 40d NAIL W/PLASTIC TAG IN THE EAST SIDE OF A UTILITY POLE N03°W 178.71' SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF AN 8" ELM S70°E 71.01' NORTH FACE OF AN ANGLE IRON FENCE CORNER POST S02°W 23.52' SOUTH 1/4 CORNER SECTION 36, T5N, R8W, IONIA COUNTY, WEST 8.25'



Signed by [Signature] Surveyor's Michigan License No. 31602

Date MARCH 17, 1995