

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u> T. <u>4</u> N. <u>9</u> W.		F-7, F-6
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S. _____, R. _____, E. _____, W. _____		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S. _____, R. _____, E. _____, W. _____		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

No 363

# FILED

FEB 23 1984

**HOWARD J. FERRIS**  
Barry County Register of Deeds  
*At 12:59 P.M.*

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

F-7 S 1/4 Corner Found: 1/2" Pinched Iron Pipe Replaced with 4"x36" Conc. Mon. with Alum. Cap	F-6 Center Section Set: 4"x36" Conc. Mon. with Alum. Cap at intersection of N-S and E-W 1/4 lines
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-7 Conc. Mon. with Alum. Cap N59°W - 24.01' - Twin 18" R. Oak N09°E - 31.38' - 30" R. Oak S73°E - 15.59' - 10" Maple S07°E - 5.15' - 10" Hickory	F-6 Conc. Mon. with Alum. Cap N25°W - 12.64' - 7" Maple N05°E - 17.00' - 10" Maple S05°E - 18.63' - 6" Maple S61°W - 35.25' - 18" R. Oak S56°W - 39.4' - Fence Corner Post
---	---

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_


SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald J. Bissell DATE 12-28-83  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1978

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET