

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
BARRY

(County)

Located In:

Corner Code ~~≠~~

- | | | | | | |
|------------------------------------|---|-----------|---|-----------|------------|
| 1. Public Land Survey | T | <u>4N</u> | R | <u>9W</u> | <u>A-8</u> |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| | T | _____ | R | _____ | _____ |
| 2. Property Controlling in Section | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | _____ |
| | S | _____ | T | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, GARY C. BILOW, in a field survey on AUGUST 29, 19 90, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

CORNER NOT ESTABLISHED IN ORIGINAL SURVEY. CORNER REFERRED TO IN 1893 COUNTY SURVEYORS RECORD BY COBB AS BEING USED TO FIND E1/4 CORNER OF SECTION 24, T4N-R10W. NO RECORD OF MONUMENT TYPE OR ACCESSORIES. RECORDS OF BARRY COUNTY ROAD COMMISSION STATE: "N1/4 CORNER SEC. 19 T4N-R9W STONE 15.15' S. OF E1/4 CORNER SEC. 24 T4N-R10W. 34° MAPLE N40E 42.5', 30° MAPLE S75E 31.7', 32° OAK N55W 38.2". CORNER RECORDED BY ROBERT J. JONKER IN 1988 AS FOUND 1/2" RE-ROD ON CENTERLINE OF N-S GRAVEL ROAD. SEE LCRC # 385 BARRY COUNTY RECORDS.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND AND ACCEPTED 8" LONG CUT AND POINTED STONE ABOVE LARGE STONE BELOW ROBERTSON ROAD. POINTED TOP WAS APPROX. 6" BELOW GRAVEL SURFACE. ROAD COMMISSION TIES TO MAPLES CHECK TO FACES OF 42" AND 36" MAPLES AFTER ALLOWING FOR TREE GROWTH. ROAD COMMISSION TIE CHECKS TO FOUND STONE AT E1/4 CORNER SECTION 24, T4N-R10W. AN OLD WIRE FARM FENCE EXTENDS EASTERLY FROM STONE AT A-8. FOUND BUT DID NOT ACCEPT 1/2" REBAR AS PREVIOUSLY RECORDED AND NOTED ABOVE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CUT AND POINTED STONE

- N42E 43.21' SET NAIL AND MICHIGAN DEPARTMENT OF NATURAL RESOURCES TAG IN SOUTHERLY FACE 42" MAPLE
- S61E 31.93' FND SPIKE IN SW FACE 36" MAPLE
- S48W 37.74' SET NAIL IN NE FACE 8" MAPLE
- N15W 77.72' SET NAIL IN NE FACE 18" HICKORY
- S50E 4.24' FOUND 1/2" REBAR PREVIOUSLY RECORDED AS A-8 (SEE LCRC #385)
- N02W 15.01' FOUND POINTED STONE AT E1/4 CORNER SECTION 24, T4N-R10W



Signed by Gary C. Bilow Date 2/15/91
 Surveyor's Michigan License No. 26453