

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

No 360

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u> T. <u>4</u> N. <u>9</u> W.		E-5, F-5
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____ E. _____ W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____ E. _____ W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

FILED

FEB 23 1984

HOWARD J. FERRIS
Barry County Register of Deeds

At 12:59 P.M.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>E-5 NW Corner Founder: "T" Iron with recorded witnesses Replaced with 1/2" Iron Pipe and Mon. Box in Pav't.</p>	<p>F-5 N 1/4 Corner Set: 4"x36" Conc. Mon. at fence intersection and 2,640' from West as called for in previous survey</p>
--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>E-5 1/2" Iron Pipe in Mon. Box S30°E - 62.07' - Twin 10" Walnut S81°W - 64.90' - Twin 12" Hickory N38°W - 52.38' - 12" Hickory On $\frac{1}{4}$ Rd. N. and S. and $\frac{1}{4}$ Rd W. also in line with Fence East</p>	<p>F-5 Conc. Mon. with Alum. Cap N22°W - 9.90' - 18" Maple N62°E - 11.00' - 24" Maple S10°W - 31.27' - 7" Sassafrass N88°W - 19.23' - 5" Maple</p>
--	--


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE 12-28-83
CLERK OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655