

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u> T. <u>4</u> N. <u>9</u> W.		E-6, G-6
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

No 359

FILED

FEB 23 1984

**HOWARD J. FERRIS**  
Barry County Register of Deeds  
At 12:54 P M

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-6 W 1/4 Corner Found: "T" Iron Replaced with 1/2" Iron Pipe and Mon. Box	G-6 E 1/4 Corner Found: Re-rod Replaced with 4"x36" Conc. Mon. Recovered Rod with Recorded Witnesses
--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-6 1/2" Iron Pipe and Mon. Box in Pav't. N85°W - 35.23' - 24" Hickory S80°E - 26.55' - Twin 12" Maple S27°E - 49.23' - Twin 14" Ash S26°W - 53.53 - 12" Basswood	G-6 4"x36" Conc. Mon. with Alum. Cap West 32.16' - 10" Ash N30°W - 51.05' - 18" Hickory N10°E - 55.63' - 6" Maple S75°E - 13.10' - 10" Oak Mon. on Fence E. and W.
---	---

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_


SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald L. Bissell DATE 12-28-83  
CHEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655