

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

No. 322

FOR CORNERS OF	Section 18	LOCATED IN--	CORNER CODE NUMBER
Irving Twp., Barry Cty.			
1. PUBLIC LAND SURVEY	T. 4	N. 9	A-5 B-5 C-5
2. PROPERTY CONTROLLING IN SECTION	T. _____	N. S., R. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____	N. S., R. _____	_____
4. LOT NO. _____, RECORDED PLAT _____			
5. PRIVATE CLAIMS _____			

FILED

OCT - 2 1981

HOWARD J. FERRIS
Barry County Register of Deeds
At 1:18 P.M.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Paul E. Van Kooten, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 18, 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

A-5: Set capped iron 10' south of centerline of Garbow Road to east and about 6 feet east of centerline of Robertson Road (15.84' South of NE corner of Section 13)

B-5: Set 1" iron on straight line between northwest and northeast corners and on line with fence to south

C-5: Set capped iron on centerline of roads to east and west and to south, centerline of two-track to north 4'+ east

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-5: NW corner <u>18</u>	B-5: N 1/4 corner <u>18</u>			
Sq. spike in W'ly side 36" Oak	N-NE 42.67'	Sq. spike in W'ly side 14" Oak	NE 8.78'	
Sq. spike in SW side 16" W Cherry	SE 46.04'	Sq. spike in S'ly side 24" Oak	W 10.92'	
Sq. spike in N'ly side 28" Maple	W-NW 101.30'	Sq. spike in N'ly side 26" Oak	SW 41.03'	
Centerline Garbow Road	N 10.00'	Centerline Garbow Road	N 97'+	
Centerline Robertson Road	W 6.00'			

C-5: NE corner

Sq. spike in SE side 26" Oak	NE 46.33'
Sq. spike in E side 18" Oak	N-NW 78.23'
Sq. spike in N side 18" Oak	W-SW 65.42'
Sq. spike in S side 26" Walnut	W-NW 102.00'


SIGNED BY Paul E. Van Kooten DATE 4-7-81
Paul E. Van Kooten - Medema, Van Kooten & Assoc., Inc.

SURVEYOR'S MICHIGAN REGISTRATION NO. 8618

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN 28, 1971
REVISED MAY 14, 1975