

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>4N</u> N. S., R. <u>9W</u> E. W.	C-4; A-4
2. PROPERTY CONTROLLING IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

NO. 368

FILED

MAR 27 1984

**HOWARD J. FERRIS**  
Barry County Register of Deeds

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Douglas W. Bonnema, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on December 27, 1983, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

C-4 from GLO notes:  
8" Oak N88°W 5 links  
7" Oak S88°E 7 links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

<p>C-4 No evidence of original bearing trees. Set corner on line with section corners and on line with fence to West and on line with centerline of trail to East.</p>	<p>A-4 Set corner mid-way and on line with Section corners. Corner is 35.64' South of E 1/4 corner, Section 12, T4N, R10W.</p>
--	--

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

<p>C-4 Capped iron. <u>E 1/4 Cor 7</u> Spike in S sde 18" Oak N80°E 11.09' Spike in W'ly sde 18" Tw. Oak N25°E 34.49' Spike in SW sde 12" Oak N45°W 30.25' Spike in S'ly sde 14" Tw. Oak S75°W 21.57' Spike in E sde 14" Tw. Oak S20°W 37.05'</p>	<p>A-4 Capped iron. <u>W 1/4 Cor Sec 7</u> Spike in SW sde 32" Oak N40°W 41.59' Spike in NE sde Tw. 14" Oak S40°E 54.34' Spike in S sde 10" Hickory East 54.06' Spike in SE sde Twin 20" Oak N45°E 65.37'</p>
---	---


SIGNED BY Douglas W. Bonnema DATE January 6, 1984

BY EXXEL ENGINEERING, INC.  
SURVEYOR'S MICHIGAN REGISTRATION NO. 12579

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET