LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF -: LGCA	TED IN -:	CORNER CODE NUMBER	
I. PUBLIC LAND SURVEY 31 T. 4	\$. R. 9 \$.	A-11, A-12	
2. PROPERTY CONTROLL- ING IN SECTION,T	N. E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION, T			
4. LOT NO, RECORDED P	LAT		
5. PRIVATE CLAIMS			REGISTER OF DEEDS STAMP AND FILING NUMBER
I, Gary C. Bilow	, do hereby ce	ertify that under requirements of	of P.A. 74, Michigan P.A. of 1970,
the corner points mentioned in lines 1 and re-established, monumented, re-monumented and rules therefore as required in the cur Bureau of Land Management or by a decrand 5 above were, in a field survey on as expressed below and in conformance we Decree of a Court of law:	2 above were, in a sted, recovered or restrent manual of surverse of a court of law.	field survey on March 25 stored as expressed below and y instructions of the United S Furthermore, that the corne 19, found, recovered, residuals.	19 62, established, in conformance with regulations states Department of the Interior, repoints mentioned in lines 3, 4 tored, established or re-established
A. Description of original monument and	accessories and/or st	ubsequent restoration:	
A-11	A-12	•	
No record since GLO	County W. Oak	Surveyor Mershon 12, S21°E, 46.21 18, N79-1/2°W, 74.58	
A-11 Found pointed stone with stones around in N-S fence line at tree row East, 17. North of NE corner section T4N, R10W.		A-12 Found 1-1/4" well porfeet NNW of 3/4" iron as corner in Record 1	n recorded
C. Description of monument for corner a:	id accessories establis	shed to perpetuate locating the	position of the corner:
A-11		A-12	
Replaced stone with 1/2"x36" rebar encased in a 4" concrete cylinder with an aluminum cap (DNR monument). N 1° W, 13.17 feet, nail & tag in 24" Oak N79°E, 10.65 feet, nail & tag in 12" Oak S11°E, 32.86 feet, nail & tag in 14" Oak S2°W, 17.2 feet, DNR monument @ NE corner Section 36		Accepted well point for northing of corner. Set DNR monument on line between E 1/4 and NE corner Sec. 36 at well point northing. S 0°E, 2.80 feet, 3/4" rod-E 1/4 cor. Sec. 36 S77°E, 46.32 feet, nail & bottlecap in 20"W.Oak S78°W, 78.02 feet, nail & bottlecap in 36"W.Oak N 1°E, 28.32 feet, nail and bottlecap in pp	
SIGNED BY		DATE	
SURVEYOR'S MICHIGAN REGISTRATI	ON NO. 26453		(SEAL)
FOR STATE AND UNITED STATES AC			
SIGNED BY	CHIEF OF SURVEY PARTY		
APPROVED AND SIGNED BY			
MICHIGAN REGISTER		D SURVEYOR	(SEAL)