

APR 04 2000

SECTION

Barry County Remonumentation  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry Co.

(County)

Located in:  
Irving Twp.

Corner Code #



2670

Page: 1 of 1  
01/02/1998 07:49A

Sandy Schondelmayer - Barry Co. LCRCR

- |                                    |             |     |
|------------------------------------|-------------|-----|
| 1. Public Land Survey              | T 4 N R 9 W | D-9 |
|                                    | T R         |     |
|                                    | T R         |     |
|                                    | T R         |     |
| 2. Property Controlling in Section | S T R       |     |
|                                    | S T R       |     |
| 3. Miscellaneous Property in Sec.  | S T R       |     |
|                                    | S T R       |     |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Robert Jonker, in a field survey on 05-10, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. survey -1830, S. Sibley, D.S.	1878, Bowen-Fd. post	1892 L. Cobb
West corrected between 20 & 29	by old bearings	B. Oak N13½E 48 lks
39.99 set post on true line	Set stake & stone 36"x8"x8"	R. Cedar 6 S70E 55 lks
A Hickory 7 N 16 E 25	W. Oak S 44 E 57	Co. Surveyor records
A Yellow Oak 28 S 11 E 44	Elm 14 N 75 E 1.11	no date
		Fd. stone for corner
		W.Oak 8 S43½E 58
		Elm 20 N75E 1.09

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Location is now in a 3'-4' fill area.  
Used county grader and found 4½' below grade the old gravel road bed.  
Found 8"x8"x36" stone set on end under gravel road bed.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
8 April '96  
BRIAN REYNOLDS COUNTY SURVEYOR

Accepted as a careful and faithful perpetuation of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Barry County monument.  
Barry Co. Remon tag W. side 18" Tw.Oak S 30° E 58.13'  
Barry Co. Remon tag E. side 14" Ash N 30° W 47.43'  
Barry Co. Remon tag W. side P. pole N 25° E 30.95'  
Barry Co. Remon tag N. side P. pole S 50° W 122.74'  
on C/L of road to South  
C/L E-W road is 5' North



Signed by Robert J. Jonker  
Surveyor's Michigan License No. 21572

Date December 01, 1997