

SURVEY & REMONUMENTATION

OCT 25 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF BARRY
 RECEIVED FOR RECORD

Aug 18 8 00 AM '93

Sandy Schondelmayer
 REGISTER OF DEEDS

For corners in
Barry
 (County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>9W</u>	<u>XB</u>
	T _____ R _____	<u>IRVING TWP</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

002075

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Gary C. Bilow, in a field survey on April 22, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

XB: Post established by U. S. Deputy Surveyor S. Sibley in 1830 - accessories: Ironwood 5 S46W 5 links and Beech 7 N46E 48 links. County Surveyor Frank Bowen records in Volume 1 Page 47 in 1878 for a survey of the South 1/2 of Section 20 "North from Southeast corner 60.19 - 15 links East of White Oak 26 - a line tree South Corrected - 20.20 Set 1/4 post - Stone for corner : Elm 36 N44W 84 and Sugar 4 S50W 39." Bowen in that same year also did a survey of Section 21 recorded in volume 1 pages 270 to 273 which shows ties to the Northwest, Southwest, East 1/4, and the establishment of the Center of Section. Corner recorded under Act 74, PA 1970 by J. McCloskey (PS #16048) in 1977 as "Found old iron - accessories: PK nail in 14" Ash N35W 31.48', PK nail in 18" Ash West 32.20', and PK nail in 10" Ash N45E 29.70'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

XB: Found 1/2" iron rod set in center of road by J. Patrick McCloskey (PS 16048) according to his hand written notes (not his Act 74 record). Intersected County Surveyor distance calls from the Northwest and East 1/4 corners (recorded this date) and dug pit. Found large oval stone with ring of smaller stones around. Distances to adjacent corners (North 2630.76 in 1878 vs 2635.23, South 2639.34 in 1878 vs 2633.52, and East 5261.52 in 1878 vs 5262.11) are reasonable and consistent. Accepted stone as the best evidence of the original GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

XB: Left Stone in place - Set 1/2" x 36" rebar encased in 4" diameter concrete cylinder and capped with a cast aluminum Michigan Department of Natural Resources Tablet
 N40E 38.35', Nail & Tag in 12" Ash
 N37W 25.26', Nail & Tag in 16" Ash
 S55E 28.69', Nail & Tag in 14" Ash
 S35W 77.77', Nail & Tag in 12" Red Oak
 S22W 58.48', Nail & Tag in 20" dying Oak
 S55E 6.74', 1/2" iron rod
 Distances are slope.



Signed by Gary C. Bilow Date 5/6/93

Surveyor's Michigan License No. 26453

10/26/93