

FEB 03 1999

SECTION

Barry County Remonumentation

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry

(County)

Located in:

Corner Code #

1. Public Land Survey

T4N R 9W

F-1 (N 1/4 corner Sec.4)

T R

Irving Twp.

T R

T R

S T R

S T R

S T R

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_



2714

Page: 1 of 1  
12/15/1998 08:24A

Sandy Schondelmayer - Barry Co. LCRCR

Register of Deeds Stamp & File Number

Steven Koerber, in a field survey on July 17, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
	6		5		4		3		2		1	
	7		8		9		10		11		12	
	18		17		16		15		14		13	
	19		20		21		22		23		24	
	30		29		28		27		26		25	
	31		32		33		34		35		36	

A. Description of original monument and accessories and/or subsequent restoration:

F-1 Corner not set by GLO surveyors

1. Kent County  
L.C.R.C. #5372 (12-5-1990)  
makes note of MVK capped rod 9.44 feet East of the  
F-13 (South 1/4 cor. Sec. 33) Bowne Twp., Kent Co.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F-1 Found 1/2" rered with cap  
K.C. monument West 9.44' South 1/4 corner Sec. 33 Bowne Twp. (F-13)  
Boat spike in W. side tri-10" Hickory S55°W 29.05'  
Nail & K.C. remon tag in W. side P. Pole N10°W 34.10'  
Nail & K.C. tag in S. side 12" Oak S60°W 36.13'  
Nail & K.C. tag in N. side 10" Ash S40°E 47.74'

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

8 Dec. 97  
BRIAN REYNOLDS

COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-1 Replaced capped rered with Barry Co. Mon. (3/4" x 24" Iron Rod with cap)  
Set nail & washer in N. side 16" Walnut N70°W 42.43'  
K.C. monument West 9.44' South 1/4 corner Sec. 33 Bowne Twp. (F-13)  
Boat spike in W. side tri-10" Hickory S55°W 29.05'  
Nail & K.C. remon tag in W. side P. Pole N10°W 34.10'  
Nail & K.C. tag in S. side 12" Oak S60°W 36.13'  
Nail & K.C. tag in N. side 10" Ash S40°E 47.74'



Signed by [Signature]  
Surveyor's Michigan License No. 39085

Date 10-12-1998