

OCT 25 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

AUG 18 8 00 AM '93

Sandy Schondelmayer
REGISTER OF DEEDS

Sequence #1

002076

Register of Deeds Stamp & File Number

For corners in Barry	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 4N R 9W	F7
	T R	IRVING TWP.
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Gary C. Bilow, in a field survey on February 09, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
F7: Post established by U. S. Deputy Surveyor S. Sibley in 1830 - accessories: White Oak 10 S4E 27 links and White Oak 12 N16-1/2W 24 links. County Surveyor Frank Bowen records in Volume 1 Page 271 in 1878 "East on random from Northwest corner 39.79 to 1/4 line - 38 N of post - found bearing - took new one : White Oak 30 N63E 28-1/2." County Surveyor L. Cobb records in 1890 records "Identified by stumps of both U.S. bearing trees and old stake. Set stone 24 x 10 x 7 with cross on top and earthen." Corner recorded under Act 74, PA 1970 by D. Bissell (PS #18655) in 1983 as "Found 1/2" Pinched iron pipe - Replaced with 4" x 36" Conc. Mon. with Alum. Cap - accessories: N59W 24.01' Twin 18" R. Oak, N9E 31.38' 30" R. Oak, S73E 15.59' 10" Maple, and S7E 5.15' 10" Hickory."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
F7: Found MDNR monument and all of Bissell's witnesses. Did not accept. Found Stone set by Cobb in 1890 4.2' North. Accepted Stone as the best evidence of the original GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F7: Left Stone in place - Set 1/2" x 24" rebar with plastic cap stamped "G.C. Bilow LLS 26453" on North side North 0.28', 1/2" capped rebar S27E 4.20', MDNR monument S65E 18.95', Nail & Tag in 10" Maple N17E 28.29', Nail & Tag in 30" Red Oak S17E 9.28', Nail & Tag in 10" Hickory N65W 20.63', Nail & Tag in twin 18" Red Oak stump



Signed by Gary C. Bilow Date 5/6/93
Surveyor's Michigan License No. 26453

10/26/93