

SURVEY & REMONUMENTATION

OCT 25 1993

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

AUG 18 8 00 AM '93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in Barry

Sandy Schondelmarer
REGISTER OF DEEDS

(County)	Located In:	Corner Code --#
1. Public Land Survey	T <u>4N</u> R <u>9W</u>	<u>F9</u>
	T _____ R _____	<u>IRVING TWP.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

002077

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary C. Bilow, in a field survey on February 09, 1993, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F9: Post established by U. S. Deputy Surveyor S. Sibley in 1830 - accessories: White Oak 6 S31W 4 links and White Oak 14 N31E 19 links. County Surveyor Frank Bowen records in Volume 1 page 270 "East on randon from Southwest corner 39.88 to 1/4 line 48 S of post - found old bearings - Stake and Stone - accessory: White Oak 18 S4W 21." Corner recorded under Act 74, PA 1970 by J. McCloskey (PS #16048) in 1977 as "Held existing fence lines and corners to south - 1/2" iron rod - accessories: PK nail in 15" Oak South 27.02'. PK nail in 32" Oak North 23.55', and PK nail in 18" Oak N40W 25.20'." Field notes obtained from Mr. McCloskey state "Set 1/2" iron rod at the split of fence posts which had fences going north and east and south and east from said posts with the centerline of the East-West trail being 0.7' south."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

F9: Found 1/2" iron rod agreeing with McCloskey's hand written notes and all of his witnesses (measurements to faces of trees - PK nails not recovered). Distance to Southeast corner is consistent with Bowen's 1878 measurements (2624.09 measured vs 2624.16). Accepted iron rod as the best evidence of the original GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F9: Left 1/2" iron rod in place
S6W 27.47', Nail & Tag in 20" Oak
N2E 24.92', Nail & Tag in 32" Oak
N35W 26.47', Nail & Tag in 21" Oak
Centerline East-West trail



Signed by Gary C. Bilow Date 5/16/93
Surveyor's Michigan License No. 26453

10/26/93