

**SURVEY &
REMONUMENTATION**

FEB 17 1998

SECTION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

002520

For Corners in BARRY Located In: _____ Corner Code # _____
(county)

1. Public Land Survey T 4N R 9W F13
SOUTH 1/4 CORNER T _____ R _____
SECTION 33 T _____ R _____
IRVING TOWNSHIP T _____ R _____
ON TOWNSHIP LINE

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
BARRY COUNTY
RECORDED
31 JUL 97 9:04 A.M.
SANDY SCHONDELMAYER
REGISTER OF DEEDS
Register of Deeds Stamp & File Number _____

I, **Brian Reynolds**, in a field survey on **14 APRIL, 1997** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE, DEPUTY SURVEYOR LUCIUS LYON, 1826, "B. O. 18 N89 1/2W 656 NO OTHER"
NOTE: THE CORRESPONDING CLOSING CORNER WAS NOT SET BY GLO. THE PLAT AND NOTES OF RUTLAND TOWNSHIP GLO SURVEY INDICATE THAT THE CLOSING CORNER EAST (G-1) IS 50 LINKS WEST OF THE STANDARD CORNER, THE CLOSING CORNER WEST (E-1) IS 24 LINKS EAST OF THE STANDARD CORNER. THUS THE THEORETICAL CLOSING 1/4 CORNER IS 13 LINKS (8.58 FEET) EAST OF THE STANDARD CORNER.
- COUNTY SURVEYOR LEE S. COBB, NOV. 18, 1889, "FOUND OLD RED CEDAR STAKE, RORK"
COUNTY SURVEYOR LIBER 2, PAGE 269. NOT PART OF THE MINUTES OF A SURVEY, BUT UNDER MISC. CORNER WITNESSES.
- LEE COBB BOOK IX PAGE 71-72, DATED NOV 18 & 19, 1889, "(FROM G-13) AT 39.05 CAME OUT OPPOSITE 1/4 SECTION CORNER OF SEC 33 OF IRVING... "FOR 1/4 SECTION POST, FOUND RED CEDAR STAKE, NO BEARINGS."
- COUNTY SURVEYOR A. N. BATEMAN, NO DATE, c. 1900, "I FOUND THE 1/4 POST BETWEEN SEC. 4 AND 33. SET TWO WITNESS STAKES, ONE 10 FT. N45°E AND THE OTHER N45°W 10 FT. COUNTY SURVEYOR NOTES L. 2, P. 294
- COUNTY SURVEYOR A. N. BATEMAN, AUG. 10, 1899, COUNTY SURVEYOR NOTES L. 3, P. 4, "A STAKE IS DRIVEN IN THE GROUND N45°E 10 FT. AND ONE N45°W 10 FT. TWO STAKES FOR THE CORNER."
- UNRECORDED SURVEY BY BRIAN REYNOLDS, P.S. 31602, DATED 31 DEC 1992, SET 3"X5' PIPE IN MARSH, AT INTERSECTION OF FENCE WEST AND APPROXIMATE AVERAGE OF FENCE NORTH. NAIL & TAG IN 12" OAK S66°45'W 161.97'
NAIL & TAG IN 12" OAK S38°10'W 234.43'
NAIL & TAG IN 12" OAK S30°56'W 261.38'
- UNRECORDED SURVEY BY ROBERT JONKER, P.S. 21572, DATED 7-20-93, 1 1/2" IRON "T" FENCE POST S55°E 24.60'
"T" IRON NORTH 14.42'
NAIL IN NW SIDE 6" WILLOW CLUMP S55°W 69.25'
NAIL & CAP S. SIDE 14" HICK S70°W 161.92'

SEE REVERSE OF THIS FORM FOR PARTS "B" AND "C", SIGNATURE AND SEAL

