

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 9 3 02 PM '93

Sandy Schondelmaier
REGISTER OF DEEDS

BARRY COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

002149

Register of Deeds Stamp & File Number

corners in
Barry County
(County)

Located In: Corner Code #
Irving Twp. _____
T 4N R 9W _____ G-3
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

Public Land Survey

Property Controlling
in Section
Miscellaneous
Property in Sec.

Lot No. _____, Recorded Plat _____
Private Claims _____

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

Robert Jonker in a field survey on February 18, 1993
I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law, established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

Description of original monument and accessories and/or subsequent restoration:

Old County surveyor notes call for a stone, 1874, see over

LCRC #106, 1973, James & King
Corner out, Reset by proportional method
12" Iron
36" tw. tree, North 20.12'
12" Oak, East 13.45'
24" Oak, N80°W 33.18'
Old fence, N,S,E,W

LCRC # 471, 1993, Robert Jonker
Nail - N.side 26"Oak N85°W 33.28'
Nail - W.side 36" Tw.Oak N0° 20.17'
Nail - S. side 12"Oak, N90°E 13.27'
C/L E-W 2 track 16½' South

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron by the witnesses listed in "A" above.

LCRC #106 and LCRC #471

And is accepted as the best available evidence of the position of the
original corner.

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with 3/4" x36" std. capped Barry County Monuments.

Use #471 witnesses.



Signed by Robert J. Jonker
Surveyor's Michigan License No. 21572

Date 11/29/93

1874, Cressy

W. Oak 9", S73½"W 88 links
R. Oak 10", N8°E 50 links
L.1, P67, County Surveyor notes

1880, Survey of Section 3 by Willson

Found corner by Cressy

B. Oak 12", N7½'E 50 links
W. Oak 12", S76°W 87 links
L.2, P299

Willson indicates on plat:
Stone & brick, in notes, "planted stone"

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION