

**SURVEY &
REMONUMENTATION**

OCT 25 1993

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

AUG 18 8 00 AM '93

COMMISSION

For corners in
Barry

Sandy Schondelmayer
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>9W</u>	<u>G8</u>
	T _____ R _____	<u>IRVING TWP.</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

002078

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Gary C. Bilow, in a field survey on March 31, 1993, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G8: Post established by U. S. Deputy Surveyor S. Sibley in 1830 - accessories: White Oak 24 S97E [sic] 14 links and White Oak 9 N37W 24 links. County Surveyor A.D. Rork records in Volume 2 page 107 in 1866 "South from Northwest corner Section 22 - 39.95 to West 1/4 post - bearings found." County Surveyor L. Cobb records in 1890 "Found stump of one U.S. tree and remains of stake - Set Stone 18 x 9 x 5 and brick - accessories: Maple 9 S88-1/2W 29 and Black Oak 7 S22-1/2 W 68-1/2." Notes obtained from P. Van Kooten (PS #08618) state "Found 2" iron in centerline Engle road on old wood fence to west - accessories: SE 32.96' spike in 20" Oak, ENE 51.46' spike in 32" Oak, NW 34.00' spike in 18" Oak, and West 19.45' spike in 42" Maple."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G8: Did not find 2" iron - found all of Van Kooten's witnesses. Pulled Van Kooten's witnesses and dug - found part of a stone - believed to be the one Cobb set in 1890 - set 1/2" x 24" rebar with plastic cap stamped "G.C. Bilow LLS 26453" one (1) foot below gravel road surface. Distance to corner G7 is consistent with Cobb's 1890 measurement (2633.51' measured vs 2633.40'). Accepted stone as the best evidence of the original GLO post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G8: Set 1/2" x 24" rebar with plastic cap stamped "G.C. Bilow LLS 26453" one (1) foot below gravel road surface
N83W 19.46', square spike in 42" Maple
N29W 33.93', square spike in 18" Oak
N80E 51.46', Nail & Tag in 32" Oak
S25E 33.61', Nail & Tag in 20" Oak stump



Signed by Gary C. Bilow Date 5/6/93
Surveyor's Michigan License No. 26453

10/26/93