

**SURVEY & REMONUMENTATION**

FEB 17 1998

**BARRY COUNTY REMONUMENTATION**

**SECTION**

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

**002521**

For Corners in <b>BARRY</b> (county)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>9W</u>	<u>G-12</u>
1/4 CORNER COMMON TO	T _____ R _____	_____
SECTIONS 33 & 34	T _____ R _____	_____
IRVING TOWNSHIP	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____ S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____ S _____ T _____ R _____	_____
4. Lot No _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
BARRY COUNTY  
RECORDED

31 JUL 97 9:05 A.M.

SANDY SCHONDELMEYER  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, **Brian Reynolds**, in a field survey on **10 DECEMBER, 1996** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- GENERAL LAND OFFICE DEPUTY SURVEYOR SYLVESTER SIBLEY, 1830, "A W. OAK 7 S64W 21 Do 6 N52E 9
- NO MENTION OF THIS CORNER COULD BE FOUND IN THE COUNTY SURVEYOR RECORDS.
- ACT 132 SURVEY BY ROBERT E. VAN LAAR, P.S. 21589, JULY 16, 1986 (L.1,P.843) "T IRON" NAIL IN SE SDE 14" OAK NE 10.20' NAIL IN N SDE 6" W. CHERRY ESE 18.42' NAIL IN W SDE 5" W. CHERRY NORTH 19.60' OLD WOOD FENCE CORNER POST 0.5' N; 0.4' EAST OF IRON.
- ACT 132 SURVEY BY DOUGLAS W. BONNEMA, P.S. #12579, SEPT. 25, 1987 (L.1, P.862) RECITE SAME WITNESSES AS IN #3 ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND "T" IRON AND ALL WITNESS TREES FROM ITEMS 3 AND 4 ABOVE. ACCEPTED "T" IRON AS BEST AVAILABLE EVIDENCE OF CORNER POSITION. REPLACED "T" IRON WITH STANDARD BARRY COUNTY REMONUMENTATION IRON AND CAP.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
- SET 20d NAIL W/REMON TAG IN THE SW ROOT OF 16" OAK N30°E 9.25'
- SET 20d NAIL W/REMON TAG IN THE SE SIDE OF 10" CHERRY N45°E 19.57'
- SET 20d NAIL W/REMON TAG IN THE S SIDE OF 12" CHERRY S88°E 17.53'
- SET 20d NAIL W/REMON TAG IN THE E SIDE OF 8" CHERRY N02°W 19.42'
- 1/2' +/- SW OF CORNER FENCE POST

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
APRIL 14, 1997 BR  
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by

*[Handwritten Signature]*

Date July 30, 1997