

**SURVEY & REMONUMENTATION**

1993

**COMMISSION**

**BARRY COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

JUL 20 11 21 AM '93

Sandy Schondelmar  
REGISTER OF DEEDS

**002058**

Register of Deeds Stamp & File Number

For corners in

<u>BARRY</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>4N</u> R <u>9W</u>	<u>G-13</u>
	T _____ R _____	<u>IRVING</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, BRIAN REYNOLDS, in a field survey on JULY, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

CORNER ESTABLISHED BY GENERAL LAND OFFICE DEPUTY SURVEYOR JOHN MULLETT, JANUARY, 1826  
"SET POST CORNER TO SECTIONS 32 & 33. W OAK 6 N70E 53 DO 7 N8W 24"

SURVEY BY BATEMAN (L.3, P.4) OCT. 23, 1899, OF SECTION 33, T4N, R9W.  
"A STAKE, S41°W 32 FT. IS 30" OAK, W 33 FT IS IRON STAKE FOR RUTLAND CORNER"  
(FOR HISTORY OF RUTLAND CORNER SEE LEE COBB BOOK IX, PG. 71)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND IRON STAKE AT G-1, T3N, R9W, AS REFERENCED BY BATEMAN, AND MORE FULLY DESCRIBED BY COBB MEASURED EAST 33 FEET AND DUG, UNCOVERING A MONUMENT IN THE FORM OF A SINGLE RED BRICK, IN UPRIGHT POSITION. ACCEPTED THE BRICK AS REPRESENTING A PROPER PERPETUATION OF THE CORNER POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

REPLACED BRICK WITH STANDARD 3/4" REMONUMENTATION IRON AND ALUMINUM CAP.

- 40D NAIL AND WITNESS TAG IN NE'LY SIDE OF 30" OAK, N30°W, 34.02'
- 40D NAIL AND WITNESS TAG IN NW'LY SIDE OF 20" OAK, N40°E, 43.97'
- 40D NAIL AND WITNESS TAG IN N'LY SIDE OF 24" OAK, S80°E, 65.22'
- 40D NAIL AND WITNESS TAG IN SE SIDE OF E'LY 8" TRUNK OF TWIN ELM, S70°W, 36.01'
- NW EDGE OF CURVE OF GRAVEL ROAD, S45°E, 2'±
- 1" PIPE (FALSE CORNER), WEST, 14.72'
- REMONUMENTATION IRON (CLOSING CORNER), WEST, 33.00'

Signed by



Date JULY 19, 1993

Surveyor's Michigan License No. 31602

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971  
31602 REVISED MAY 12, 1975  
REVISED JAN., 1983

