

STATE OF MICHIGAN
 COUNTY OF BARRY
 RECEIVED FOR RECORD

Dec 9 3 02 PM '93

Sandy Schondelmaier

REGISTER OF DEEDS

002146

Register of Deeds Stamp & File Number

Barry County Remonumentation
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

or corners in

Barry County
 (County)

Located In: Irving Twp. Corner Code #

Public Land Survey

T 4N R 9W H-4

T R

T R

T R

Property Controlling
 in Section

S T R

Miscellaneous
 Property in Sec.

S T R

Lot No. , Recorded Plat
 Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Robert Jonker in a field survey on Feb. 18, 1993
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
 lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
 current manual of survey instructions of the United States Department of the Interior, Bureau of Land
 Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
 Court of Law; established, re-established, monumented, re-monumented, recovered, found as
 expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
 on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 Not set in original GLO survey
 LCRC #471, Jonker, 1993, Capped iron @ int. of 1/4 lines.
 NE. Cor. "U" box S85°W 55.44'
 Nail, SW side 8" Elm S40°E 43.95'
 Nail, S. side 18" Maple N75°E 54.73'
 C/L steel sign post N65°W 76.83'

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found capped iron per LCRC #471 as listed in "A" above.

And accepted as the best available evidence of the position of the original
 corner.

SURVEY &
 REMONUMENTATION

APR 05 1994

COMMISSION

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Replaced with 3/4"x36" std. capped Barry County Monument.

NE. Cor. "U" box S85°W 55.44'
 Nail-SW side 8" Elm S40°E 43.95'
 Nail-S side 18" Maple N75°E 54.73'
 C/L steel sign post N65°W 76.83'
 C/L of N-S road is 11.7'W
 C/L gravel road to West is 8'±N



Robert J. Jonker

Recorded by Robert J. Jonker Date 11/29/93
 Surveyor's Michigan License No. #21572