

STATE OF MICHIGAN  
 COUNTY OF BARRY  
 RECEIVED FOR RECORD

Dec 9 3 02 PM '93

Sandy Schondelmar  
 REGISTER OF DEEDS

002150

Register of Deeds Stamp & File Number

Barry County Remonumentation  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

Corner in

Barry Co.  
 (County)

Located In:  
 Irving Twp.

Corner Code #

Public Land Survey

T 4N R 9W

H-5

Property Controlling  
 in Section  
 Miscellaneous  
 Property in Sec.

S T R  
 S T R  
 S T R  
 S T R

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

Robert Jonker in a field survey on Feb. 18, 1993

hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

LCRC #341, 1982, James A. Reda, P.S. #12590  
 Found 1/2" solid, down 12", set small bt. spike on top.

Cap & nail in N.E. side 12" Hickory S35°E 77°37'  
 Cap & Nail in NE side 12" Oak N30°W 47.21'  
 Cap & nail in E. side 22" Oak N15°W 100.44'  
 C/L stop sign post N60°E 48.92'  
 on C/L, N-S & E Blk.top  
 On fence, West

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found capped 3/4" round iron #18055 in Mon. box.  
 Checked o.k. by witnesses listed in "A" above for LCRC #341

And is accepted as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced with 3/4"x36" standard capped Barry Co. Mon. in mon. box.

Cap & Nail in NE side 12" Hickory S35°E 77.37'  
 Cap & Nail in NE side 12" Oak N30°W 47.21'  
 Cap & Nail in E side 22" Oak N15°W 100.44'  
 C/L stop sign post N60°E 50.84'  
 2'E of N-S pavement.  
 4'S of pavement to East.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

SURVEY &  
 REMONUMENTATION  
 APR 05 1994  
 COMMISSION



Witnessed by Robert J. Jonker  
 Robert J. Jonker #21572  
 Surveyor's Michigan License No.

Date 11/29/93