

Barry County Remonumentation  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
 COUNTY OF BARRY  
 RECEIVED FOR RECORD

DEC 9 3 02 PM '93

Sandy Schondelmar  
 REGISTER OF DEEDS

**002151**

Register of Deeds Stamp & File Number

corners in  
Barry Co.  
 (County)

Located in:  
Irving Twp. Corner Code #  
 \_\_\_\_\_

Public Land Survey	T <u>4</u> N R <u>9</u> W	<u>I-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Robert Jonker in a field survey on Feb. 18, 1993  
 I hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:  
 Per LCRC #342, 1982, James A. Reda, P.S. #12590. Found 1/2" solid rod, down 9", set small bolt spike on top.  
 Cap & nail in NW side Db1. 12" Oak N50°E 52.45'  
 Cap & Nail in NW side 24" Oak S 30.21'  
 Cap & nail in N side Db1. 8" Elm S60°E 55.65'  
 Cap & Nail in W side 18" Oak N30°E 29.60' - stump 1993  
 On C/L B.T., E & W, fence south

SURVEY &  
 REMONUMENTATION  
 APR 05 1994  
 COMMISSION

Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found corner as recorded in LCRC #342, as listed in "A" above.  
 And is accepted as the best available evidence of the position of the original corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Replaced with 3/4"x24" std. capped Barry County monuments.  
 Cap & nail in NW side Db1. 12" Oak N50°E 52.45'  
 Cap & Nail in NW side 24" Oak S 30.21'  
 Cap & nail in N side Db1. 8" Elm S60°E 55.65'  
 Cap & nail in W. side 18" Oak N30°E 29.60' - stump 1993  
 On C/L B.T., E & W, fence South.



Signed by Robert J. Jonker Date 11/29/93  
 Surveyor's Michigan License No. #21572