

SURVEY & REMONUMENTATION

NOV 6 4 1996

COMMISSION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

AUG 20 11 27 AM '96

Sandy Schondelmayer  
REGISTER OF DEEDS

002390

Register of Deeds Stamp & File Number

For corners in

BARRY  
(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>4N</u> <u>R9W</u>	<u>I-13</u>
CORNER COMMON TO SECTIONS	T _____ R _____	_____
4 & 35 IRVING TOWNSHIP	T _____ R _____	_____
ON TOWNSHIP LINE	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, BRIAN REYNOLDS, in a field survey on 31 MARCH, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration

GENERAL LAND OFFICE: L. LYON, D.S., 1826(R9W, P.148)  
W. OAK 30 N39 1/2E 164 Do. 24 N39W 2.39

NO OTHER RECORDED HISTORICAL INFORMATION AVAILABLE FOR THIS CORNER

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE, BUT NO SUPPORTING DOCUMENTATION, NEAR I-1, T3N R9W.. MEASUREMENTS ALONG TOWNSHIP LINE ONE MILE WEST AND TWO MILES EAST, TYING IN FOUND STANDARD AND CLOSING CORNERS AND OCCUPATION LINES, INDICATE THE OCCUPATION FENCE NORTH, APPROXIMATELY 23 FEET EAST OF FOUND PIPE CORRESPONDS WITH SECTION LINE BETWEEN SECTION 34 AND 35, T4N R9W. A VAGUE OCCUPATION LINE SOUTH (MARGIN BETWEEN TWO CULTIVATED FIELDS) WOULD BE CONSISTANT WITH EITHER THE FOUND PIPE OR A POSITION DETERMINED BY THE GOVERNMENT JOG, APPROXIMATELY 20 FEET EAST OF THE FOUND PIPE. MEASUREMENTS TO OCCUPATION LINES AND RESTORED CORNERS 1/4 MILE WEST (MARGIN BETWEEN FIELDS), 1/2 MILE WEST (OLD OCCUPATION FENCE), AND ONE MILE WEST (RESTORED CORNERS), IN CONFLICT, ONE WITH ANOTHER. THE FENCE 1/2 MILE WEST IS WITHIN 1/2 FOOT OF MIDWAY BETWEEN THE RESTORED CORNER AT G-1 AND THE POSITION DETERMINED BY THE GOVERNMENT JOG. THE OCCUPATION LINE 1/4 MILE WEST, VAGUE AT BEST, WOULD TEND TO CONFIRM THE POSITION OF THE FOUND PIPE, BEING WITHIN 2 FEET OF MIDWAY BETWEEN THE FOUND PIPE AND THE OLD OCCUPATION FENCE. TIED IN I-2 AND PLAT MONUMENTS, RESULTS CONFIRM I-13 AT FENCE LINE NORTH. RESTORED I-1 AT INTERSECTION OF PLAT LINE AND TOWN LINE. RESTORED I-13 AT GOV'T JOG, DISREGARDING FOUND IRON PIPE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
- SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 30" MAPLE N68°W 78.74'
- CENTER OF A 3/4" IRON BAR IN A 12"x12" CONCRETE FENCE CORNER POST N6°W 30.86'
- SET 40d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A UTILITY POLE N54°E 91.56'
- SET 40d NAIL W/PLASTIC TAG IN THE SOUTH SIDE OF A 6" MAPLE N66°E 73.11'
- SET 40d NAIL W/PLASTIC TAG IN THE NORTH SIDE OF A UTILITY POLE S65°E 92.50'
- I-1 T3N, R9W, RUTLAND TOWNSHIP WEST 2.64'

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

APRIL 10, 1995 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

Signed by [Signature]  
Surveyor's Michigan License No. 31602

Date AUGUST 16, 1996

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

