

OCT 27 1994

COMMISSION

BARRY COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN COUNTY OF BARRY RECEIVED FOR RECORD

SEP 26 11 21 AM '94

Sandy Schondelmarer REGISTER OF DEEDS

For corners in

BARRY (County)

Located In:

Corner Code #

- 1. Public Land Survey T 4N R 9W M-4 IRVING TOWNSHIP E 1/4 COR SEC 12 2. Property Controlling in Section S T R 3. Miscellaneous Property in Sec. S T R

002211

Register of Deeds Stamp & File Number

- 4. Lot No. Recorded Plat 5. Private Claims

Grid table with columns A-L and rows 2-13. Cell 4,12 contains a small circle.

I, BRIAN REYNOLDS, in a field survey on 8 SEPT, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. CORNER ESTABLISHED BY GENERAL LAND OFFICE DEPUTY SURVEYOR LUCIUS LYON, 1826 HICKORY 7 S39W 64 THORN 7 N30W 32 2. NO MENTION OF CORNER IN COUNTY SURVEYOR RECORDS OR ROAD COMMISSION RECORDS, PLANS, OR NOTES 3. LAND CORNER RECORDATION CERTIFICATE #320 & 321 (SAME DATA ON BOTH FORMS) BY PAUL E. VAN KOOTEN, P.S. #8618, FILED 10-2-1981 "SET 1/2" CAPPED REROD ON CENTERLINE BIT. CONCRETE ROAD IN LINE WITH TREE AND FENCE ROW TO WEST. "SQ. SPIKE IN W'LY SIDE 28" MAPLE N-NE 90.04'; SQ. SPIKE IN N SIDE 30" MAPLE W 29.54'; SQ. SPIKE IN E'LY SIDE 14" OAK S-SW 56.49'; SQ SPIKE IN E'LY SIDE 14" ASH S-SE 58.00'."

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 8" COLD CHISEL WITH PLASTIC CAP (CAP NOT LEGIBLE) FOUND SPIKE IN 28" MAPLE BY VAN KOOTEN, CHECKED AND CONFIRMED DIRECTION AND DISTANCE, OTHER WITNESSES BY VAN KOOTEN PRESENT BUT NAILS OVERGROWN, DIRECTION AND DISTANCE TO SCAR AT NAIL CHECKED AND CONFIRMED. ACCEPTED FOUND CAPPED CHISEL AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION. REPLACED WITH STANDARD REMON IRON AND CAP, AND INSTALLED MONUMENT BOX.

ACT 345 BARRY COUNTY REMONUMENTATION APPROVED BY PEER REVIEW AT A MEETING HELD ON 12 SEPT. 94 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- SET STANDARD BARRY COUNTY REMONUMENTATION IRON (3/4"X36"W/ALUMINUM CAP) AND INSTALLED MONUMENT BOX FOUND OLD NAIL IN N SIDE OF UTILITY POLE N87W 50.59' SET 40d NAIL & TAG IN W SIDE OF AN 8" MAPLE N30E 58.67' SET 40d NAIL W/REMON TAG IN E SIDE OF A 10" HICKORY S21W 67.63' SET 40d NAIL W/REMON TAG IN N SIDE OF AN 18" OAK S71E 58.57' APPROXIMATELY ON CENTERLINE OF NORTH-SOUTH BITUMINOUS ROAD



Signed by [Signature] Surveyor's Michigan License No. 31602

Date SEPT 14, 1994