

OCT 27 1994

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

SEP 26 11 21 AM '94

For corners in
BARRY

Sandy Schindelmarer
REGISTER OF DEEDS

(County)	Located In:	Corner Code #
IRVING TOWNSHIP	T 4N R 9W	M-9
SE COR SEC 24 ON RANGE LINE	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

002215

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

BRIAN REYNOLDS 8 SEPT 94

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. CORNER ESTABLISHED BY GENERAL LAND OFFICE DEPUTY SURVEYOR LUCIUS LYON, 1826. ELM 7 S52W 16 W.O. 20 N24W 49
- 2. RECORD OF CORNER IN COUNTY SURVEYOR RECORDS, FOUND STAKE AND ONE BEARING, TOOK NEW: ELM 10 S74 1/2W 1.03; W. OAK 8 N65 1/2E 89 (BOWEN 24 NOV 1875, LIBER 1 OF COUNTY SURVEYOR'S RECORD, PAGE 96)
- 3. UNRECORDED SURVEY BY MARINUS MULDER, c1985, FOUND SPIKE, NO WITNESSES AVAILABLE
- 4. UNRECORDED SURVEY BY BRIAN REYNOLDS, P.S. #31602, 1992, FOUND SPIKE, NO WITNESSES RECORDED

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND SPIKE 8" LONG, ABOUT 1/2 FOOT BELOW THE SURFACE OF THE GRAVEL ROAD
ACCEPTED FOUND SPIKE AS BEST AVAILABLE EVIDENCE OF CORNER LOCATION
REPLACED SPIKE WITH STANDARD BARRY COUNTY REMON IRON AND CAP

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

12 Sept. '94
BRIAN REYNOLDS

BR
COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION IRON (3/4"X36"W/ALUMINUM CAP)

- SET 40d NAIL W/REMON TAG IN S SIDE OF A 10" BLACK WALNUT, EAST, 22.64'
- SET 40d NAIL W/REMON TAG IN TOP CENTER OF A CORNER FENCE POST, N31E, 45.56'
- SET 40d NAIL W/REMON TAG IN E SIDE OF UTILITY POLE, N29W, 80.90'
- SET 40d NAIL W/REMON TAG IN S SIDE OF A 10" ELM, N84W, 35.43'

APPROXIMATELY ON CENTER OF GRAVEL ROAD N-S (FIGHTER ROAD)
IN LINE WITH OLD FENCE WEST



Signed by: *[Signature]*

Date: SEPT 14, 1994

Surveyor's Michigan License No. 31602