

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>4N</u> N. S., R. <u>10W</u> E. W.	<u>K-5, J-7, J-6, I-6</u> <u>K-7, K-6</u>
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

NO. 199

FILED

OCT 22 1976

HOWARD J. FERRIS
Garry County Register of Deeds
At 9:15 AM
REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Douglas W. Bonnema, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on June 28, 19 76, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

K-5 Set 3/4" iron on 4 gravel rd. in line with fence to North.	J-7 Set 3/4" iron by holding previous witnesses.	J-6 Set 1/2" re-rod at intersection of 1/4 lines.	I-6 Set 3/4" iron on line and midway between Section corners.
--	--	---	---

K-7 Found square spike.
Checks with all's by w/d.

K-6 Found large stone. Set 3/4"
iron at fence corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-5 Nail in sde Tw. 14" Cherry WNW 89.28' Nail in sde cor fe post WSW 71.56'	J-7 Nail in sde 24" Walnut North 22.72' Nail in sde P. Pole SSW 40.82' Nail in sde 20" Walnut WNW 102.41' SW cor hse NNE 99.22'	J-6 Nail in sde 8" Sass. W. 16.44' Nail in sde 28" Oak East 8.78' Nail in sde 24" Oak South 52.77' Fence to South E 6' E-W fence North 2'	I-6 Nail in top fe post NW 99.46' Nail in top fe post WSW 56.19' Nail in top fe post SW 98.85' N-S fence West 56.0' fe line to W extend East North 82.0'
K-7 Nail in sde 12" Oak SW 55.65' Nail in sde 18" Oak NE 57.36' Nail in sde db1 18" Oak ESE 53.47' On tree line to N-S	K-6 Nail in sde 24" Oak ENE 23.32' Nail in sde 14" W. Cherry NNE 36.78' Nail in sde 14" Oak WSW 32.33'		


SIGNED BY Douglas W. Bonnema DATE October 19, 1976

EXCEL ENGINEERING, INC. SURVEYOR'S MICHIGAN REGISTRATION NO. 12579

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____