

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 4 N. S., R. 10 E. W.	M-2 M-3
2. PROPERTY CONTROLLING IN SECTION	T. N. S., R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S., R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

No. 14

FILED

JAN 31 1972

HOWARD J. FERRIS
Barry County Register of Deeds
At 9:20 A.M.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Douglas W. Bonnema do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on January 4, 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-2 No information of value available to help in finding corner.

M-3 3/4" Iron - 1969
NE SEC. 12

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-2 Set corner on line with fence to North and on line with center of trail to South, and on line with traces of fence to West.

M-3 Found 3/4" Iron - ties from 1969 check good.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-2 2" iron pipe
Nail in side of 24" twin Maple SW 18.38'
Nail in side of 10" Wild Cherry N-NE 20.16'
Nail in side of 10" Wild Cherry S-SE 21.0'
Fence to East is approx. 45' South

M-3 3/4" Iron
Nail in face of P. pole S-SW 102.13'
Nail in face of T. pole W 26.95'
Nail in face of 20" Walnut N-NE 47.97'
Nail in face of 12" Walnut E-SE 21.61'
Center of road South 36'


SIGNED BY Douglas W. Bonnema DATE 1-27-72

Douglas W. Bonnema
MEDEMA, VAN KOOTEN & ASSOCIATES, INC.
SURVEYOR'S MICHIGAN REGISTRATION NO. 12579

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



PAGE 38

SURVEYOR'S MICHIGAN REGISTRATION NO. _____