

B. (M-7) CONTINUED.

SOUTH TO THE ADJACENT STANDARD CORNER LOCATIONS, IT CREATES UNACCEPTABLE DISCREPANCIES WITH THE GLO RECORD. RECENTLY MONUMENTED CORNERS FOR SECTIONS ON BOTH SIDES OF THE RANGE LINE WERE RECOVERED FROM M-8 TO M-4 INCLUSIVE, BUT IT IS APPARENT THAT THEY WERE PLACED BY SINGLE PROPORTIONATE MEASUREMENT BETWEEN THE ERRONEOUS M-8 AND M-3. I DID NOT ACCEPT THESE MONUMENTS. I ACCEPTED THE FENCE ALONG THE NORTH LINE OF SECTION 24 AS EVIDENCE OF THE ORIGINAL CORNER POSITION AND LOCATED 6 POINTS AT REGULAR INTERVALS ALONG IT TO A DISTANCE OF ABOUT 275' WEST OF ROBERTSON ROAD. I RECOVERED NO FENCE POSTS. I COMPUTED A LEAST SQUARES LINE OF BEST FIT THROUGH THESE POINTS AND PROJECTED IT EASTERLY TO ITS INTERSECTION WITH THE RANGE LINE AND REESTABLISHED THE CORNER AT THIS LOCATION. THE RANGE LINE WAS RECONSTRUCTED BY RUNNING A STRAIGHT LINE BETWEEN THE STONE AT M-8 AND M-3 AS RECORDED BY BONNEMA.