

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>36</u>	T. <u>4</u> N. R. <u>10</u> W.	M-11                  M-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gary C. Bilow, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March 25, 1982, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

<p><b>M-12</b> Tied to centerline of Irving Road in a 1963 road and bridge construction survey but not described. Described as 3/4" solid iron in a survey recorded in Liber 001 page 186 Nail in side of 36" Oak, SW 77.42 Nail in side of PP, N 31.17 Nail in side of 20" Oak, E 45.95</p>	<p><b>M-11</b> No record since GLO</p>
--	--

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p><b>M-12</b> Found 3/4" iron as described above. Iron is recorded as W 1/4 corner Section 31, T4N, R9W. Accepted for E 1/4 corner section 36, T4N, R10W.</p>	<p><b>M-11</b> Found pointed stone with stones around in N-S fence line, 17.2 feet south of NW corner section 31, T4N, R9W</p>
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p><b>M-12</b> Left 3/4" iron as corner, witnesses remain as above adding:  N 0°E, 2.80 feet, DNR monument at W 1/4 corner section 31, T4N, R9W</p>	<p><b>M-11</b> Replaced stone with 1/2"x36" rebar encased in 4" concrete cylinder with 4" aluminum cap (DNR monument) S68°E, 10.68 feet, nail &amp; RLS cap in 10" R. Oak S32°E, 17.47 feet, nail &amp; tag in 14" Oak N 1°E, 30.53 feet, nail &amp; tag in 24" Oak N 2°E, 17.2 feet, DNR monument at NW cor. Sec. 31</p>
---	---

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 26453 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)