

APR 08 1996

Barry County Remonumentation

Nov 20 8 35 AM '95

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmayer
REGISTER OF DEEDS

For corners in

Barry (County)	Located In:	Corner Code #
1. Public Land Survey	4N 10W T ___ R ___ T ___ R ___ T ___ R ___ T ___ R ___	A-6(W 1/4, 18) Thornapple Twp. _____ _____
2. Property Controlling in Section	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___ S ___ T ___ R ___	_____ _____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

002314

Register of Deeds Stamp & File Number

I, Steven Koerber, in a field survey on August 31, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-6 GLO (no post set) 1. No date
Barry County Road Comm.
Iron
Cor. iron post N45°W 40.11'
Fence post S45°E 32.4'
Fence Post S45°W 39.1'
GR. Cable TR N45°E 45.11'

(Additional info. see back of sheet)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-6 Found Capped rerod 1/2"x18"
Found 1 1/4" Iron Pipe South 2.67'
Solid Iron rod North 1.23'
Found 48" Stump S15°W 156.0±
Found MBT box (SE cor.) N45°W 45.8'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
OCT 10, 1995 ALLEGAN CO. BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-6 Replaced capped rerod with Barry Co. Mon. (3/4" x 24" Iron Rod with cap)
Set 3/4" x 24" Iron rod with Allegan Co. Remonumentation witness cap S 45° E 66.98'
Set 3/4" x 24" Iron rod with Allegan Co. Remonumentation witness cap N 50° E 58.20'
Set 3/4" x 24" Iron rod with Allegan Co. Remonumentation witness cap N 45° W 48.93'
Set 3/4" x 24" Iron rod with Allegan Co. Remonumentation witness cap S 50° W 46.45'
M-6, Leighton Twp., Allegan County, corner is South 2.90'

Signed by Steven C. Koerber Date 11-13-1995
Surveyor's Michigan License No. 39085



2. Nov. 29, 1977.
Exxel Eng.
Recorded survey L.1, Pg.452, (Barry Co.)
Bolt spike witnessed
Nail & tag in N'ly side RR tie post SE 42.27'
C/L MBT underground cable box NE 45.16'
3/4" Iron (E 1/4 cor. Sec. 13) S 3.89'
C/L Street sign N-NW 47.35'
N. Edge Stop sign W-SW 50.94'
3. August 13, 1981
LCRC #324 (Barry Co.)
Paul Van Kooten
Found capped iron on centerline of roads N-S-E-W
Nail & tag in N. side corner fence post SE 41.75'
1 1/4" Iron pipe S 2.65'
SE corner MBT box NE 46.30'
Nail & cap in SE side 38" Beech S-SW 155.66'
4. April 14, 1981
Medema Van Kooten & Assoc.
Recorded survey L.1, Pg. 691 (Barry Co.)
Capped Iron
Nail & Cap in side 38" Beech S-SW 155.66'
SE cor. MBT Box NE 46.30'
5. Exxel Eng. notes
Found MVK capped Iron Oct 1987
Nail in N. side fence post SE 41.75'
SE cor. MBT box NE 46.30'
Nail in SE side 38" Beech S-SW 155.66'
1 1/4" Iron S 2.65'
Bt. spike N 1.20'
6. 1987
Gackler Road Plans
Barry Co. Rd. Comm.
Note 3 corners in road used North corner
Cor. Fence post N45°W 40.9'
Cor. Fence post S45°E 32.3'
Cor. Fence post S45°W 39.1'
Tele. pole N45°E 45.9'