

APR 08 1996

COMMISSION

Barry County Remonumentation

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

Nov 20 8 35 AM '95

Sandy Schindelmayr

REGISTER OF DEEDS

002321

Register of Deeds Stamp & File Number

For corners in

Barry (County) Located In: Corner Code #
1. Public Land Survey T 4N R 10W A-8 (W 1/4,19) Thornapple Twp.
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R
4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Cell (8,1) contains a dot.

Steven Koerber August 31 95
I, Steven Koerber, in a field survey on August 31, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- A-8 GLO (no post set) I. Dec. 23, 1980 LCRC Rec. as No. 307 (Barry Co) Carl Shangraw Found 5/8" iron rod PK nail in 28" Walnut S20°E 87.57' PK nail in 8" Walnut East 66.57' Street sign S40°W 38.50'
2. Recorded Survey Carl Shangraw (Barry Co.) Dec. 22, 1980 L.1, Pg. 639 same wits as LCRC # 307

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-8 Found rerod 1/2"x18" in mon. box Rerod in mon. box South 6.82' (East 1/4 Sec. 24, T4N, R11W)

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

AUGUST 14, 1995 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-8 Replaced rerod with Barry Co. Mon. (3/4" x 24" Iron Rod with cap)
Set PK nail & Allegan Co. Remon. Tag in NW side P. Pole S 40° W 189.26'
Set PK nail & Allegan Co. Remon. Tag in S. side P. Pole N 60° W 112.65'
Nail & Allegan Co. Remon. Tag in S. side 16" Basswood N 90° E 261.78'
SW corner house foundation (Gar. corner) N 60° E 164.44'
M-8, Leighton Twp., Allegan County, corner is South 6.82'

Signed by Steven C. Koerber Date 11-13-1995
Surveyor's Michigan License No. 39085

