

APR 04 2000

Barry County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry

(County)

Located in:

Corner Code #

4N

10W

A-10(W 1/4, 30)

1. Public Land Survey

T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_

Thornapple Twp.

2. Property Controlling in Section

S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

3. Miscellaneous Property in Sec.



2843

Page: 1 of 1  
12/07/1999 08:36

Darla K. Burahdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

I, Steven Koerber, in a field survey on August 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6		5		4		3		2		1
3											
4	7		8		9		10		11		12
5											
6	16		17		16		15		14		13
7											
8	19		20		21		22		23		24
9											
10	30		29		28		27		26		25
11											
12	31		32		33		34		35		36
13											

A. Description of original monument and accessories and/or subsequent restoration:

A-10 Corner not set by GLO

- L.C.R.C. 481 October 27, 1993 by Douglas Bonnema, Found rerod in mon. box, Found PK nail in N. side 18" ash SW 76.70'; Found PK nail in S. side P.Pole West 97.07'; Set nail in S. side 20" Ash E-NE 176.18'; Rerod in mon. box South 9.63'; Chiseled "X" in top South end conc. F.E.S. SE 60.73'; C/L 'X' ± Patterson Road & Jackson Road, South 7'±.
- August 15, 1997 Act 132 survey, Douglas Root, Exxel Engineering, Same wits as No. 1 above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

A-10 Found rerod in mon. box

Found PK nail S. side P.Pole West 97.07

Found rerod in Mon. box (M-10, Leighton Twp., Allegan Co.) corner is 9.63' South

C/L 'X' Patterson and Jackson Roads South 7'±

Replaced rerod in Mon. box with Barry Co. Mon. (3/4" x 24' Iron rod with cap)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-10 Replaced rerod with Barry Co. Mon. ( 3/4" x 24" Iron Rod with cap)

Allegan Co. Remon. Tag in N. side 6" Sassifrass S 85° W 49.45'

Set nail & Barry Co. Remon. Tag in S. side P.Pole N 20° W 290.85'

Set nail & Barry Co. Remon. Tag in N side 15" Hickory S 70°E 255.59'

Set Nail & Barry Co. Remon. Tag in W side P. Pole S 5° E 425.32'

Allegan Co. Iron Rod with Remon cap in Mon. box (M-10, Leighton Twp., Allegan Co.) corner is 9.63' South

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
12 Oct 98  
BRIAN REYNOLDS  
COUNTY SURVEYOR



Signed by Steven C. Koerber

Date 11-19-1999

Surveyor's Michigan License No. 39085