

APR 04 2000

Barry County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry
(County)

Located In:

Corner Code #

4N 10W A-11(SW 30)

1. Public Land Survey

T___ R___

Thornapple Twp.

T___ R___

T___ R___

T___ R___

2. Property Controlling
in Section

S___

T___ R___

S___

T___ R___

3. Miscellaneous
Property in Sec.

S___

T___ R___

S___

T___ R___

Darla K. Burghdoff- Barry Co. LCRCR



2844

Page: 1 of 1
12/07/1999 08:36

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Steven Koerber, in a field survey on August 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | |
|----|----|---|---|----|---|---|----|---|---|----|---|----|----|
| 1 | | | | | | | | | | | | | |
| 2 | 6 | | | 5 | | | 4 | | | 3 | | 2 | 1 |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | | 8 | | | 9 | | | 10 | | 11 | 12 |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | | 17 | | | 16 | | | 15 | | 14 | 13 |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | | 20 | | | 21 | | | 22 | | 23 | 24 |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | | 29 | | | 28 | | | 27 | | 26 | 25 |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | | 32 | | | 33 | | | 34 | | 35 | 36 |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

- A-11 GLO (set corner) West 79.13, West Boundary 16 lks N. of post Sylvester Sibley D.S. 1830, A.W. Oak 30, S60°E 49; Do. 7, N46°E 42
 - January 3, 1995 Act 132 survey L.2, Pg.100-101, Douglas Bonnema, Exxel Engineering, Rerod in Mon. Box, found rerod in Mon. box. South 10.60'; Set PK nail in NW side P.Pole N40°E 58.78'; Set spike in N. side Bitternut Hickory N85°E 45.05'; Set spike in N. side 24" Twin Cherry S85°W 102.28'; Set PK nail in SW side P.Pole S30°E 148.52'
 - August 15, 1997 Act 132 surveys L.2, Pg. 220-221-222, Douglas Root, Exxel Engineering, Same wits as No. 1 above.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-11 Found rerod in mon. box
Found PK nail SW side P.Pole S30E 148.52'
Found rerod in Mon. box (M-11, Leighton Twp., Allegan Co.) corner is 10.60' South
Found PK nail in NW side P.Pole N40°E 58.78'
Found spike in N side Bitternut Hickory N85°E 45.05'
Replaced rerod in Mon. box with Barry Co. Mon. (3/4" x 24' Iron rod with cap)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-11 Replaced rerod with Barry Co. Mon. (3/4" x 24" Iron Rod with cap)

| | | |
|---|--------|---------|
| Allegan Co. Remon. Tag in N. side 24' Hickory | S 85°E | 45.29' |
| Allegan Co. Remon. Tag in SE side P.Pole | N 40°E | 58.87' |
| Allegan Co. Remon. Tag in S side P.Pole | N85°W | 154.74' |
| Allegan Co. Remon. Tag in E side P. Pole | S10°E | 148.15' |
| Capped rerod | East | 33.00' |

 Allegan Co. Iron Rod with Remon cap in Mon. box (M-11, Leighton Twp., Allegan Co.) corner is 10.60' South

Signed by Steven C. Koerber
Surveyor's Michigan License No. 39085

Date 11-19-1999

