

APR 04 2000

Barry County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry

(County)

Located In:

Corner Code #

4N 10W

A-12(W1/4, 31)

Thornapple Twp.

1. Public Land Survey

T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_  
T \_\_\_ R \_\_\_

2. Property Controlling  
in Section

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_ T \_\_\_ R \_\_\_  
S \_\_\_ T \_\_\_ R \_\_\_



2845

Page: 1 of 1  
12/07/1999 08:30

Darla K. Burghdoff - Barry Co. LGRCR

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Steven Koerber, in a field survey on August 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6	5			4			3			2	1
3												
4	7	8			9			10			11	12
5												
6	18	17			16			15			14	13
7												
8	19	20			21			22			23	24
9												
10	30	29			28			27			26	25
11												
12	31	32			33			34			35	36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- A-12 Corner not set by GLO 1. Jan 26, 1866 A.D. Rork W. Oak 12, N10 1/4E 1.35 1/2; Do. 12, S80°E 10 1/2
- 2. December 7, 1981 L.C.R.C. No. 329, by Paul Van Kooten, Found 3/4" iron 6.5' East of centerline and approximately in line with trail to East; Nail & tag in NW side 24" Oak NE 43.58', Nail & tag in N'y side 18" Hickory E-SE 27.15'; Top USGS BM NW 51.08'
- 3. January 3, 1995 Act 132 survey L.2, Pg.100-101, Douglas Bonnema, Exxel Engineering, Iron in mon. box, Set PK nail in top of guard post S45°W 25.46'; Set PK nail in top of guard post N45°W 27.32'; Set PK nail in top of guard post N45°E 24.43'; Set PK nail in top of guard post S45°E 25.72'; Mon. box is 1.5'± E of C/L B.T.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- A-12 Found 3/4" iron in mon. box  
Found PK nail in top of guard post S45°W 25.46'  
Found PK nail in top of guard post N45°W 27.32'  
Found PK nail in top of guard post N45°E 24.43'  
Found PK nail in top of guard post S45°E 25.72'  
Mon. box is 1.5'± E of C/L B.T.  
Capped rod East 33.00'  
Replaced 3/4" iron in Mon. box with Barry Co. Mon. (3/4"x 24' Iron rod with cap)

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON  
12 Oct 98 BR  
BRIAN REYNOLDS COUNTY SURVEYOR



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- A-12 Replaced 3/4" iron with Barry Co. Mon. ( 3/4" x 24" Iron Rod with cap)  
Found PK nail in top of guard post S45°W 25.46'  
Found PK nail in top of guard post N45°W 27.32'  
Found PK nail in top of guard post N45°E 24.43'  
Found PK nail in top of guard post S45°E 25.72'  
Mon. box is 1.5'± E of C/L B.T.  
Capped rod East 33.00'  
Allegan Co. Iron Rod with Remon cap in Mon. box (M-12, Leighton Twp., Allegan Co.) corner is 5.30' South

Signed by [Signature]  
Surveyor's Michigan License No. 39085

Date 11-19-1999