

DEC 9 3 02 PM '93

Sandy Schondelmarper
 REGISTER OF DEEDS

002155

Barry County Remon.
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry
 (County)

Located In: Thorn-	Corner Code #
apple Twp.	F-10
T 4N R 10W	
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Robert Jonker, in a field survey on February 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 No set in original G.L.O. surveys.
 Nothing on record at Reg. of Deeds
 or at Road Comm. or at County Surveyors Office

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Set 1/2" capped rerod @ int. of 1/4 lines and accepted as best evidence of corner location.

SURVEY &
 REMONUMENTATION
 APR 05 1994
 COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Replaced with 3/4"x24" std. Barry Co. Capped Monument
 NW cor conc foundation to gas tank S 45° E 22.62'
 NE cor conc foundation to gas tank S 55° E 27.18'
 C/L top pump S 65° E 30.12'
 PK on top conc fence post (lying dn) S 15° W 35.55'
 on E-W field division line



Signed by Robert J. Jonker
 Surveyor's Michigan License No. JONKER LAND SURVEYS 21572

Date November 29, 1993