

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 9 3 02 PM '93

Sandy Schindelmaier
REGISTER OF DEEDS

Barry County Remon.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Barry
(County)

Located In: Thorn-
apple Corner Code #
T 4N R 10W F-11
T R
T R
T R
S T R
S T R
S T R
S T R

002156

Register of Deeds Stamp & File Number

- 1. Public Land Survey
- 2. Property Controlling in Section
- 3. Miscellaneous Property in Sec.
- 4. Lot No. , Recorded Plat
- 5. Private Claims

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Robert Jonker, in a field survey on April 10, 1993, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

L.C.R.C. #231, Exxel Eng. 1978
Found "T" Iron
Nail in side 34" Maple SW 44.76'
Nail in side 18" Walnut N 29.98'
Nail in side 14" Maple SE 54.48'
Barry Co. Road Comm. = No info.
Barry Co. Surveyor = No info.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found "T" Iron in pavement
Fd N & E, side 22" Walnut N 05° W 30.0
Set nail - W'y side 18" Maple S 30° E 54.3'
Set PK SE side P. pole S 50° W 119.45'
SE cor. utility pad N 35° W 48.46'

Accepted as best evidence of corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced with std. 3/4"x24" Barry Co. Capped Monument
Found N & E, side 22" Walnut N 05° W 30.0'
Set nail - W'y side 18" Maple S 30° E 54.3'
Set Pk SE side P. pole S 50° W 119.45'
SE corner utility pad N 35° W 48.46'
E-W C/L is 1' South
on C/L to South

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by Robert J. Jonker
JONKER LAND SURVEYS 21572
Surveyor's Michigan License No.

Date November 29, 1993