

DEC 9 3 02 PM '93

Sandy Schindelmaier

REGISTER OF DEEDS

002160

Register of Deeds Stamp & File Number

Barry County Remon.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry
(County)

Located In: Thorn- Corner Code #
apple

1. Public Land Survey	T	<u>4N</u>	R	<u>10W</u>	<u>G-10</u>
	T		R		
	T		R		
	T		R		
2. Property Controlling in Section	S		T		R
	S		T		R
3. Miscellaneous Property in Sec.	S		T		R
	S		T		R

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Robert Jonker in a field survey on February 10, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10, Old county surveyor notes call for a stone - 1902.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10, Found "T" Iron

Found Nail S. side 30" Elm clump N 90° E 41.38'
Found Nail S. side P. pole N 90° W 128.78'
C/L Stop sign post N 60° W 39.5'
Set PK E. side E. sign post N 25° W 96.04'

Accepted as the best evidence of the corner location.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-10, Replaced with 3/4"x24" capped std. Barry Co. Monument

Found Nail S. side 30" Elm clump N 90° E 41.38'
Found Nail S. side P. pole N 90° W 128.78'
C/L stop sign post N 60° W 39.5'
Set PK E. side E. sign post N 25° W 96.04'


On C/L tree line to the East & field division line to the West & 1' West of N-S pavement.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by Robert J. Jonker
JONKER LAND SURVEYS 21572
Surveyor's Michigan License No. _____

Date November 29, 1993