

DEC 9 3 02 PM '93

Barry county Remon.
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Sandy Schondelmayer
REGISTER OF DEEDS

002157

Register of Deeds Stamp & File Number

For corners in
Barry
(County)

Located In: **Thorn-apple** Corner Code **##**
T 4N R 10W G-11
T _____ R _____
T _____ R _____
T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____
S _____ T _____ R _____

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Robert Jonker, in a field survey on February 10, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-11, L.C.R.C. #147, Exxel Eng. 1974, they found "T" Iron which checks prev. witnesses
Nail in side T. pole WSW 46.72'
Nail in side T. pole NW 55.6'
Nail in side T. pole SE 43.42'
BT spike N 3.5'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-11, Found Exxel capped iron in mon. box with "T" iron
Fd PK nail S. side P. pole N 75° W 138.06'
Fd N & B.C. N. side P. pole S 50° E 43.42'
Set PK in NE'ly side P. pole N 40° W 188.53'
Set Nail E. side 16" Elm S 20° W 131.82'

Accepted as best evidence of corner location.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-11, Replaced with 3/4"x24" std. capped Barry Co. Monument in Mon. box
Fd PK nail S. side P. pole N 75° W 138.06'
Fd N & B.C. N. side P. pole S 50° E 43.42'
Set PK in NE'ly side P. pole N 40° W 188.53'
Set Nail E. side 16" Elm S 20° W 131.82'
C/L "X" is 5' East & 1' North on C'L to N, E, S, W

SURVEY &
REMONUMENTATION

APR 05 1994

COMMISSION



Signed by Robert J. Jonker
JONKER LAND SURVEYS
Surveyor's Michigan License No. 21572

Date November 29, 1993