

REMONUMENTATION

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

APR 08 1996

LAND CORNER RECORDATION CERTIFICATE

DEC 15 2 07 PM '95

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

COMMISSION

Sandy Schondelmayer
REGISTER OF DEEDS

BARRY

(County)

Located In:

Corner Code #

1. Public Land Survey	T	4N	R	10W	H-5
1/4 CORNER COMMON TO	T		R		
SECTIONS 10 & 15 THORNAPPLE	T		R		
TOWNSHIP	T		R		
2. Property Controlling	S		T	R	
in Section	S		T	R	
3. Miscellaneous	S		T	R	
Property in Sec.	S		T	R	

002346

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

BRIAN REYNOLDS

6 SEPT.

95

I, BRIAN REYNOLDS, in a field survey on 6 SEPT., 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R10W,P.172) "WEST CORRECTED 40.02"
 A SUGAR 12 N41E 21 A BEECH 8 S39W 18
 COUNTY SURVEYOR RECORDS: COBB 1888 (THORN. F.B., P.84) "STONE 24"x12"x12" POINTED AT EACH END FOR STAKE" BLACK WALNUT 10 N8 1/2E 1.21
 LAND CORNER RECORDATION CERTIFICATE: #216 BY D. BONNEMA P.S.#21579 "FOUND 1" IRON PIPE. CHECKS WITH PREVIOUS WITNESSES" NAIL IN FACE TRIPLE 14" OAK SSE 31.50' NAIL IN FACE DBL 12" WALNUT ESE 64.08' NAIL IN FACE 12" WALNUT NORTH 51.33' NAIL IN FACE 10" WALNUT WNW 36.78'
 ACT 132 SURVEYS: BY D. BONNEMA, P.S.#21579, L.1,P.403 L.1,P.419 L.1,P.451 L.1,P.844 L.1,P.852 L.1,P.969 WITNESSES SAME AS IN L.C.R.C. #216 ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" IRON PIPE FROM BONNEMA'S WITNESSES (WALNUT NORTH & WALNUT WNW) PROBED AND EXCAVATED A LARGE AREA IN SEARCH OF STONE BY COBB, FOUND NOTHING ACCEPTED FOUND 1" IRON PIPE AS BEST EVIDENCE OF CORNER POSITION REPLACED PIPE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

ACT 345 BARRY COUNTY REMONUMENTATION
 APPROVED BY PEER REVIEW AT A MEETING HELD ON

9/11/95 BR
 BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"x36"W/ALUMINUM CAP)
 SET 20d NAIL W/REMON TAG IN THE SOUTH SIDE OF A 14" BLACK WALNUT N6°E 51.90'
 SET 20d NAIL W/REMON TAG IN THE SOUTH SIDE OF A 16" BLACK WALNUT S82°E 50.38'
 SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF AN 18" BLACK WALNUT N65°W 37.33'
 SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A UTILITY POLE S55°E 89.98'
 CENTERLINE EAST-WEST GRAVEL ROAD (GARBOW) IS SOUTH 19'+/-



Signed by [Signature]
 Surveyor's Michigan License No. 31602

Date 12/15/95