

BARRY COUNTY REMONUMENTATION

APR 04 2000

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY Located In: _____ Corner Code # _____
(county)

1. Public Land Survey T 4N R 10W H-10
CENTER OF SECTION 27 T _____ R _____
THORNAPPLE TOWNSHIP T _____ R _____



2865
Page: 1 of 1
12/27/1999 01:44P

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

Register of Deeds Stamp & File Number

3. Miscellaneous S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Brian Reynolds, in a field survey on 22 APRIL, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.
NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- THIS CORNER WAS NOT SET BY THE GENERAL LAND OFFICE.
 - PRIVATE NOTES: OF ROBERT JONKER, P.S., #21572, c. 1986, SKETCH OF SECTION BREAKDOWN, SHOWS BEARINGS & DISTANCES AROUND EXTERIOR OF SECTION 27 & BEARINGS & DISTANCES ON 1/4 LINES NORTH-EAST-SOUTH.

*** NO OTHER HISTORICAL INFORMATION, PUBLIC OR PRIVATE, AVAILABLE FOR THIS CORNER ***

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
TRAVERSED ALL OF SECTION 27 AND COMPUTED INTERSECTION OF 1/4 LINES. FOUND "T" IRON 2'+ BELOW GRADE. "T" IRON HAS APPARENTLY BEEN HIT WITH A PLOW & WAS LEANING TO THE WEST.
FOUND "T" IRON LIES 0.05' NORTH & 0.06' WEST OF INTERSECTION OF 1/4 LINES.
ACCEPTED INTERSECTION OF 1/4 LINES AS BEST AVAILABLE EVIDENCE OF CORNER POSITION.
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AT INTERSECTION OF 1/4 LINES. LEFT "T" IN PLACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/PLASTIC TAG IN THE SOUTHEAST SIDE OF A WOODEN FENCE CORNER POST S10°W 3.83'
SET 20d NAIL W/PLASTIC TAG IN THE NORTHWEST SIDE OF A WOODEN ANCHOR POST S82°W 9.66'
NO OTHER NEARBY WITNESSES AVAILABLE
G-10 LIES S89°42'27"W, 2661.44'
I-10 LIES N89°42'27"E, 2649.33'
H-9 LIES N00°25'40"W, 2640.60'
H-11 LIES S00°25'40"E, 2621.94'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

14 June '99
BRIAN REYNOLDS
COUNTY SURVEYOR



Signed by Brian Reynolds
Surveyor's Michigan License No 31602

Date Dec 27, 1999