

APR 04 2000

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For Corners in BARRY (county) Located In: Corner Code #
1. Public Land Survey T 4N R 10W H-11
1/4 CORNER COMMON TO SECTIONS 27 & 34 THORNAPPLE TOWNSHIP
2. Property Controlling in Section
3. Miscellaneous



2866 Page: 1 of 1 12/27/1999 01:44P

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 1-13. Cell (11, H) contains a solid black circle.

I, Brian Reynolds, in a field survey on 21 DECEMBER, 1999 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1. GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R10W, P.169) W. OAK 14 N87E 5 Do. 14 N6W 11
2. COUNTY SURVEYOR RECORDS: A.C. WILSON, FEB. 26, 1867 (L.2, P.122) "ORIGINAL BEARINGS FOUND" NO WITNESSES
3. CONSUMERS POWER COMPANY: NO NAME, 8-71 & 11-71 (F.B., P.863) "FND "T" IRON 6" BELOW BLKTP."
4. LAND CORNER RECORDATION CERTIFICATE: #147, BY DOUGLAS W. BONNEMA, P.S. 12579, 7-25-1974 "BOAT SPIKE" NAIL IN SDE 16" MAPLE NORTH 23.48' NAIL IN SDE 14" TW SAS. SW 27.65' NAIL IN SDE 30" OAK SE 63.20'
5. ACT 132 SURVEY: BY DOUGLAS W. BONNEMA, P.S. 12579, 8-2-1974 (L.1, P.244-245) SAME WITNESSES AS IN #4 ABOVE
6. ACT 132 SURVEY: BY ROBERT E. VANLAAR, P.S. #21589, 2-10-1978 (L.1, P.450) SAME WITNESSES AS IN #4 ABOVE EXCEPT 14" TWIN SASSAFRAS DISTANCE IS 77.65'
7. ACT 132 SURVEY: BY ROBERT E. VANLAAR, P.S. #21589, 5-22-1980 (L.1, P.604-605) SAME WITNESSES AS IN #4 ABOVE EXCEPT 14" TWIN SASSAFRAS DISTANCE IS 77.65'
8. ACT 132 SURVEY: BY DOUGLAS W. BONNEMA, P.S. #12579, 8-19-1983 (L.1, P.751-756) SAME WITNESSES AS IN #4 ABOVE
9. ACT 132 SURVEY: BY DOUGLAS W. BONNEMA, P.S. #12579, 9-5-1985 (L.1, P.820) SAME WITNESSES AS IN #4 ABOVE
10. ACT 132 SURVEY: BY ROBERT J. JONKER, P.S. #21572, 3-21-1988 (L.1, P.887-891) SAME WITNESSES AS IN #4 ABOVE EXCEPT 14" TWIN SASSAFRAS DISTANCE IS 77.65'
11. ACT 132 SURVEY: BY DOUGLAS W. BONNEMA, P.S. #12579, 11-10-1988 (L.1, P.915) SAME WITNESSES AS IN #4 ABOVE
12. ACT 132 SURVEY: DONALD L. HERREMA, P.S. #24597, 10-20-1992 (L.2, P.67-68) SAME WITNESSES AS IN #4 ABOVE EXCEPT 14" TWIN SASSAFRAS DISTANCE IS 77.65' AND SET NAIL IN NW SDE 15" OAK S-SW 34.93'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND BOAT SPIKE AND ALL WITNESSES RECITED IN ITEMS 4-12 ABOVE. TRAVERSED ALL OF SECTION 27, TYING OCCUPATION. FOUND CORNER CONFORMS WITH CORRESPONDING SECTION CORNERS AND LOCAL OCCUPATION. ACCEPTED FOUND BOAT SPIKE AS BEST AVAILABLE EVIDENCE OF CORNER POSITION. REPLACED FOUND BOAT SPIKE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT AND INSTALLED MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4" X 36" IRON) WITH ALUMINUM CAP.
SET 20d NAIL W/REMON TAG IN THE EAST SIDE OF A 30" OAK S06°E 33.95'
SET 20d NAIL W/REMON TAG IN THE NORTHEAST SIDE OF A 40" OAK S53°E 63.62'
SET 20d NAIL W/REMON TAG IN THE WESTSIDE OF A 12" PINE N46°E 46.70'
FOUND RIGHT-OF-WAY IRON SOUTH 32.80'
FOUND NAIL IN EAST SIDE OF A 30" MAPLE N02°E 23.40'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
14 June, 99
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature] Surveyor's Michigan License No 31602

Date DEC 27, 1999