

COMMISSION

BARRY COUNTY REMONUMENTATION

APR 08 1996

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 15 2 07 PM '95

Sandy Schondelmar
REGISTER OF DEEDS

002341

Register of Deeds Stamp & File Number

For corners in

BARRY

(County)

Located In:

Corner Code #

- 1. Public Land Survey T 4N R 10W
CORNER COMMON TO SECTIONS 2,3,10, & 11 THORNAPPLE TOWNSHIP
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

BRIAN REYNOLDS in a field survey on 6 SEPT., 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R10W, P.168) A BEECH 6 S59E 22 Do.7 N43W 11
LAND CORNER RECORDATION CERTIFICATE: #120 BY D. BONNEMA, P.S.#12579 "FOUND "T" IRON.
CHECKS WITH PREVIOUS WITNESSES" PK IN SDE T.POLE NE 74.13'
NAIL IN SDE 12" WALNUT ESE 86.15' NAIL IN SDE 28" MAPLE SW 44.16'
COUNTY ROAD COMMISSION: WITNESSES SAME AS IN L.C.R.C.#120 ABOVE
ACT 132 SURVEYS BY D. BONNEMA, P.S.#12579 L.1,P.343-344 L.1,P.477 L.1,P.567 L.1,P.662 L.1,P.692 L.1,P.719
L.1,P.827-828 L.1,P.949-965 L.1,P.980-982 L.2,P.59 WITNESSES SAME AS IN L.C.R.C.#120 ABOVE
ACT 132 SURVEY BY R. E. VAN LARR, P.S.#21589 WITNESSES SAME AS IN L.C.R.C.#120 ABOVE
ACT 132 SURVEY BY D.L. HERREMA, P.S.#24597 WITNESSES SAME AS IN L.C.R.C. #120 ABOVE
PLAT OF THORNAPPLE RIVERSIDE BY O. CUTSHAW Jr. (L.5,P.55) CORNER REFERENCED NO WITNESSES

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND "T" IRON FROM BONNEMA'S WITNESSES (MAPLE SW & T. POLE NE).
ACCEPTED FOUND "T" IRON AS BEST EVIDENCE OF CORNER POSITION
REPLACED FOUND "T" IRON WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
9/11/95 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
SET 40d NAIL W/PLASTIC TAG IN THE SOUTHWEST SIDE OF A UTILITY POLE S35°E 75.60'
FOUND NAIL IN THE NORTHEAST SIDE OF A 40" MAPLE S45°W 45.19'
FOUND "PK" IN THE SOUTH SIDE OF A UTILITY POLE N65°E 74.15'
FOUND NAIL IN THE SOUTHWEST SIDE OF A 22" BLACK WALNUT S71°E 86.11'
CORNER IS IN LINE WITH TREE LINE SOUTH
CENTERLINE STRIPE IS 1.2'+/- NORTH



Signed by [Signature]
 Surveyor's Michigan License No. 31602

Date 12/15/95