

APR 08 1996

COMMISSION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 15 2 07 PM '95

Sandy Schondelmarjer
REGISTER OF DEEDS

002347

Register of Deeds Stamp & File Number

For corners in

BARRY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 4N R10W I-5
- CORNER COMMON TO SECTIONS 10,11,14, &15 THORNAPPLE TOWNSHIP
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

BRIAN REYNOLDS, in a field survey on 6 SEPT., 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830(R10W,P.166) A. W. OAK 8 S48 1/2E 10 Do. 6 S73W 20
COUNTY SURVEYOR RECORDS: CRESSEY, 1874(L.1,P.35) A W. O. STUMP 16 S75W 1.66 1/2 W.O. 6 S51 1/2E 1.00
LAND CORNER RECORDATION CERTIFICATE: #146 BY D. BONNEMA, P.S. #12579, "SET IRON BY HOLDING LINE AND DOUBLING DISTANCE FROM IRON AT S1/4 COR AND IRON AT SW COR, E1/2, SW1/4. SET 3/4" CAPPED IRON."
NAIL IN SDE 12"OAK ESE 43.37' NAIL IN SDE 16"ASH WEST 54.28'
NAIL IN SDE 26"ASH NNE 143.0' E&W FENCE NORTH 2.8'
ACT 132 SURVEY BY D. BONNEMA, P.S. #12579, (L.1,P.322) WITNESSES ARE SAME AS IN L.C.R.C.#146 ABOVE
ACT 132 SURVEY BY WILLIAM R. BYL, P.S. #23502, (L.1,P.656-657) WITNESSES ARE SAME AS IN L.C.R.C.#146 ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE FROM BONNEMA'S WITNESSES (OAK ESE, ASH WEST, & FENCE NORTH)
SEARCHED FOR OTHER EVIDENCE OF MONUMENTATION, FOUND NOTHING. CRESSY'S DISTANCE TO J-5 IS SIGNIFICANTLY LONGER THAN BONNEMA'S; CRESSY'S NOTES INDICATE THAT HE FOUND NO LOCAL EVIDENCE OF CORNER, THAT HE REESTABLISHED BY RUNNING LINE FROM I-6 NORTH TO MEANDER POST AT THORNAPPLE RIVER AND SET CORNER ON LINE, PRESUMABLY AT PROPORTIONAL DISTANCE. IT SEEMS CERTAIN THAT THE CORNER SET BY BONNEMA IS A NUMBER OF FEET EAST OF THE POSITION BY CRESSY; HOWEVER, GIVEN THE RESULTING SECTION MEASUREMENTS, IT APPEARS BONNEMA'S POSITION MORE ACCURATELY APPROXIMATES THE POSITION SET BY THE GENERAL LAND OFFICE SURVEY.
ACCEPTED FOUND PIPE AS BEST EVIDENCE OF CORNER POSITION
REPLACED FOUND PIPE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
FOUND NAIL IN THE SOUTH SIDE OF A 14" BLACK WALNUT N83°W 54.16'
FOUND NAIL IN THE SOUTH SIDE OF AN 18" OAK S78°E 43.41'
I-4 T 4 N, R 10 W LIES N00°11'27"W 2628.80' ACT 345 BARRY COUNTY REMONUMENTATION
J-5 T 4 N, R 10 W LIES S89°28'56"E 2642.35' APPROVED BY PEER REVIEW AT A MEETING HELD ON

9/11/95
BRIAN REYNOLDS COUNTY SURVEYOR



Signed by [Signature]
Surveyor's Michigan License No. 31602

Date 12/15/95