

SURVEY & REMONUMENTATION

APR 26 1995

COMMISSION

Barry County Remonumentation
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

DEC 8 8 15 AM '94

Sandy Schondelmayer
REGISTER OF DEEDS

002250

Register of Deeds Stamp & File Number

corners in Barry (County)	Located In:	Corner Code #
Public Land Survey	T <u>4N</u> R <u>10W</u>	<u>J-9 (N¹, 26)</u> <u>Thornapple Twp.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Lot No. _____, Recorded Plat _____
Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

John C. Bueche, in a field survey on September, 19 94,
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:
 J-9 GLO Sibley, DS, 1830 LCRC #406, March, 1990
 A.W. Oak 8" N 20° E 23 lks. 1 1/2" iron pipe
 A.W. Oak 8" S 66° W 14 lks. "T" cut in stone E 36.36'
 Bowen 1875 stone, Nail & cap in E side 10" Pine S 5° W 34.58'
 can & stake Cut nail in W side 10" Pine S 35° E 64.75'
 1 1/4" solid iron S 70° E 24.82'
 C/L Irving Rd. E 107.7'±

Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 J-9 Found 1 1/2" iron
 Dug 2' deep, did not find stone, As per above wit.
 can or stake

And is accepted as the best available evidence of the position of the original corner

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

DEC 6, 1994 BR
BRIAN REYNOLDS COUNTY SURVEYOR

Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 J-9 Replaced 1 1/2" x 15" iron with Barry Co. Mon. (3/4" x 24" Pin with Cap)
 Nail & Barry Co. Remon. Tag in N side 42" Walnut S 85° E 26.57'
 Nail & Barry Co. Remon. Tag in W side 12" Pine S 35° E 64.65'
 Nail & Barry Co. Remon. Tag in E side 12" Pine S 5° W 34.57'
 Nail & Barry Co. Remon. Tag in N side 10" Walnut S 55° W 45.46'
 C/L Irving Rd. E 107.7'±
 3/4" iron W 14.30'
 1 1/4" solid iron S 70° E 24.82'
 Brush & tree row S 4'±

Signed by John C. Bueche
Surveyor's Michigan License No. 13027

Date 10-26-94

