

APR 08 1996

COMMISSION

BARRY COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
COUNTY OF BARRY  
RECEIVED FOR RECORD

DEC 15 2 07 PM '95

Sandy Schondelmarjer  
REGISTER OF DEEDS

002344

Register of Deeds Stamp & File Number

For corners in

BARRY  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 4N R 10W K-4  
1/4 CORNER COMMON TO  
SECTIONS 11 & 12  
THORNAPPLE TOWNSHIP
- 2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BRIAN REYNOLDS, in a field survey on 6 SEPT., 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R10W,P.162)  
A. W. OAK 7 S58 1/2E 5 Do. 8 N51W 6 1/2  
LAND CORNER RECORDATION CERTIFICATE: #120 BY D. BONNEMA, P.S.#12579, "SET 3/4" IRON BY HOLDING DISTANCES FROM ORIGINAL GOVERNMENT NOTES" NAIL IN SDE 26" OAK SE 3.58'  
NAIL IN SDE 30" OAK NW 4.65' NAIL IN SDE 14" W. CHERRY NORTH 28.49' E&W FNC NORTH 4' N&S FNC EAST 3'  
COUNTY ROAD COMMISSION: RECITES SAME WITNESSES AS BONNEMA IN L.C.R.C.#120 ABOVE  
ACT 132 SURVEY: BY D. BONNEMA, P.S.#12579 L.1,P.932-933 RECITE SAME WITNESSES AS IN L.C.R.C.#120 ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" IRON PIPE FROM BONNEMA'S WITNESSES(OAK NW, OAK SE, & FENCES)  
EXCAVATED AND PROBED AN EXTENSIVE AREA AROUND BONNEMA'S IRON AND AROUND FENCE CORNER,  
FOUND NO EVIDENCE OF ORIGINAL MONUMENT.  
ACCEPTED FOUND 3/4" IRON PIPE AS BEST EVIDENCE OF CORNER POSITION.  
REPLACED FOUND 3/4" PIPE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

ACT 345 BARRY COUNTY REMONUMENTATION  
APPROVED BY PEER REVIEW AT A MEETING HELD ON

9/11/95 BR  
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)  
FOUND NAIL W/BOTTLE CAP IN THE SOUTHWEST SIDE OF A 28" OAK S58°E 3.58'  
FOUND NAIL W/BOTTLE CAP IN THE SOUTHWEST SIDE OF A 30" OAK N50°W 4.65'  
SET 20d NAIL W/REMON TAG IN THE NORTHWEST SIDE OF A 10" MAPLE N27°E 22.87'  
SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 6" OAK S47°W 24.61'  
SET 20d NAIL W/REMON TAG IN THE NORTH SIDE OF A 12" OAK S33°E 31.90'  
EAST-WEST FENCE IS NORTH 4'+/- NORTH-SOUTH FENCE IS EAST 3'+/-



Signed by [Signature]  
Surveyor's Michigan License No. 31602

Date 12/15/95