

APR 08 1996

BARRY COUNTY REMONUMENTATION

STATE OF MICHIGAN
COUNTY OF BARRY
RECEIVED FOR RECORD

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 15 2 07 PM '95

For corners in

BARRY
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 4N R10W
CORNER COMMON TO
SECTIONS 11,12,13, &14
THORNAPPLE TOWNSHIP K-5
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Sandy Schondelmayer
REGISTER OF DEEDS

002349

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, BRIAN REYNOLDS, in a field survey on 6 SEPT., 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GENERAL LAND OFFICE: SYLVESTER SIBLEY, D.S., 1830 (R10W,P.161)
A. W. OAK 20 S46 1/2W 250 Do. 18 S77W 291
LAND CORNER RECORDATION CERTIFICATE: #199 BY D. BONNEMA, P.S.#12579 "SET 3/4" IRON ON C/L GRAVEL RD. IN LINE WITH FENCE TO NORTH" NAIL IN SDE Tw. 14" CHERRY WNW 89.28' NAIL 19N SDE COR FE POST WSW 71.56'
ACT 132 SURVEY: BY D. BONNEMA, P.S.#12579 (L.1,P.932-933) RECITE SAME WITNESSES AS IN L.C.R.C.#199 ABOVE
ACT 132 SURVEY: BY E.J. GLAZA, P.S.#9548 (L.1,P.395-396) N25°W 49.19' TO NAIL IN EAST SIDE OF 3" DOGWOOD N74°W 89.35' TO BOTTLE CAP IN SW SIDE 14" ELM S64°W 71.60' TO BOTTLE CAP ON SE SIDE OF FENCE POST
ACT 132 SURVEY: BY R.E. VAN LAAR, P.S.#21589(L.1,P.398-400) RECITE SAME WITNESSES AS BONNEMA IN L.C.R.C.#199 ABOVE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE FROM BONNEMA'S WITNESSES(FNC. NORTH, FNC. POST WSW, & TW. CHERRY WNW) SEARCHED FOR ANY OTHER CORNER MONUMENTATION, FOUND NOTHING. ACCEPTED FOUND 3/4" PIPE AS BEST EVIDENCE OF CORNER POSITION. REPLACED FOUND PIPE WITH STANDARD BARRY COUNTY REMONUMENTATION MONUMENT.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON

9/11/95 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET STANDARD BARRY COUNTY REMONUMENTATION MONUMENT (3/4"X36"W/ALUMINUM CAP)
FOUND CAPPED IRON SOUTH 33.00' FOUND CAPPED IRON NORTH 33.00'
SET 20d NAIL W/REMON TAG IN THE WEST SIDE OF A UTILITY POLE S2°W 29.50'
SET 20d NAIL W/REMON TAG IN THE NORTHWEST SIDE OF A 12" ELM N52°E 34.06'
SET 20d NAIL W/REMON TAG IN THE SOUTH SIDE OF A 12" ELM N78°E 75.82'
CENTERLINE OF EAST-WEST BITUMINOUS ROAD (GARROW) LIES SOUTH 0.5'+/-



Signed by [Signature]

Date 12/15/95

Surveyor's Michigan License No. 31602