

APR 04 2000

Barry County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry	Located In:	Corner Code #
(County)		
1. Public Land Survey	4N 10W	L-3(South 1/4, 1)
	T R	Thornapple Twp.
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

2805
Page: 1 of 12/07/1999 09
Darla K. Burghdoff - Barry Co. LGRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven Koerber, in a field survey on June 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L
1											
2	6	5	4	3	2						
3											
4	7	8	9	10	11						
5											
6	18	17	16	15	14						
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

A. Description of original monument and accessories and/or subsequent restoration:

- | | | | | | |
|-----|-------------------------------------|----|--------------------------------|----|--------------------------|
| L-3 | GLO | 1. | Lcc Cobb Oct 11, 1910 | 2. | DeKeyser files (no date) |
| | S. Sibley 1830 D.S. | | Found old stake | | Per Vankooten |
| | A.W. Oak 7 S21E 80 | | Set stone 36"x18"x9" & brick | | 3/4" iron |
| | Do. 14 N83W 38 | | B. Oak 20 N8 1/4°E 29 1/2 lks. | | 1' N. of C/L blacktop |
| | GLO dist 39.85 ch. | | | | Twin 5" Maple ENE 47.62' |
| | 2630.10' | | | | 18" W. Cherry S. 45.96' |
| | (Additional info. on back of sheet) | | | | P.Pole SE 73.75' |
| | | | | | 36" Maple SW 46.55' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- L-3 Found stone (dimensions 31"x19"x9" & brick per Cobb notes No. 1 above) 1.3' below road surface, 0.65' South & 0.09' East of found 3/4" Iron pipe per No. 2 above.
Dist to East 2620.68'
Dist to West 2621.61'

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
8 JUNE 98 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | | | |
|-----|--|---------|--------|
| L-3 | Replaced stone with Standard Barry Co. Mon. (3/4" x 24" Iron Rod with cap) | | |
| | Set nail & washer in E. side P. Pole | N13°W | 30.41' |
| | Set nail & washer in W. side P. Pole | S 30°E | 72.73' |
| | Set nail & washer in N. side twin 18" Maple | N 75° E | 48.28' |
| | Fnd. nail & washer in E. side 22" Oak | S20°W | 34.40' |

Signed by [Signature]
Surveyor's Michigan License No. 39085

Date 11-22-1999

