

APR 04 2000

Barry County Remonumentation

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Barry
(County)

Located in: 4N 10W Corner Code # M-3 (SE, 1)
Thornapple Twp.

1. Public Land Survey T R
T R
T R
T R

2. Property Controlling S T R
in Section S T R

3. Miscellaneous S T R
Property in Sec. S T R



2806
Page: 1 of 2
12/07/1999 08:36

Darla K. Burghdoff - Barry Co. LCRCR

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Steven Koerber, in a field survey on June 3, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2			1
3												
4	7		8		9		10		11			12
5												
6	18		17		16		15		14			13
7												
8	19		20		21		22		23			24
9												
10	30		29		28		27		26			25
11												
12	31		32		33		34		35			36
13												

A. Description of original monument and accessories and/or subsequent restoration:

- M-3 GLO 1826 L.Lyons DS W.Oak 24 S9w 50. Do. 15 N27W 28
1. Stake & a pile of stones- No date
 2. January 13, 1972 Act 132 survey Liber 1, Pg. 12. Paul Van Kooten, 3/4" iron pipe, P.pole S-SW 102.13', 20" Walnut N-NE 47.97', T.Pole West 26.95', 12" Walnut E-SE 21.61'.
 3. January 27, 1972 L.C.R.C. #14 Douglas Bonnema 3/4" iron same wits as No. 2 above
 4. May 22, 1980 Act 132 survey Liber 1, Pg. 607 Dougas Bonnema same wits as No. 3 above
(See back of page for additional information)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- M-3 Found 3/4" pipe
Fnd nail & MDNR tag in W. face 27" Walnut N30°E 42.58'
Fnd nail & MDNR tag in N. face 12" Walnut N45°W 21.77'
Fnd nail & MDNR tag in S. face 16" twin Walnut S60°E 22.00'
South 55.57' found 3/4" iron pipe at northwest corner of Section 7, T4N, R9W, (A-3, Irving Twp., Barry Co.)
South 36' centerline of Parmalee Road.

ACT 345 BARRY COUNTY REMONUMENTATION
APPROVED BY PEER REVIEW AT A MEETING HELD ON
8 JUNE 98 BR
BRIAN REYNOLDS COUNTY SURVEYOR

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- M-3 Set Barry Co. Mon. (3/4" x 36" Iron Rod with cap) in mon.box
Fnd nail & MDNR tag in W. face 27" Walnut N30°E 42.58'
Fnd nail & MDNR tag in N. face 12" Walnut N45°W 21.77'
Fnd nail & MDNR tag in S. face 16" twin Walnut S60°E 22.00'
South 55.57' found 3/4" iron pipe at northwest corner of Section 7, T4N, R9W, (A-3, Irving Twp., Barry Co.)
South 36' centerline of Parmalee Road.

Signed by [Signature]
Surveyor's Michigan License No. 39085

Date 11-22-1999

