

PART "A" (CONTINUED)

3. RECORDS OF COUNTY ROAD COMMISSION (NO NAME OR DATE)
 STONE: 20" WALNUT N30W 58.2'
 COR. IRON POST S2E 33.1'
 24" MAPLE N50W 37.2'
 Y.S. COR. 4.6' S (NOTE: THIS APPARENT REFERENCE TO THE CORRESPONDING CLOSING CORNER AS A "YANKEE SPRINGS" CORNER IS IN ERROR ONLY TO THE TOWNSHIP NAME; THE TRUE NAME OF THE ADJOINING TOWNSHIP IS IRVING)

017-3

4. LAND CORNER RECORDATION CERTIFICATE NO. 427, BY GARY C. BILOW, P.S. #26453, AUGUST 29, 1991. "...FOUND AND ACCEPTED 1/2" DIAMETER IRON BAR WHICH FITS ROAD COMMISSION DISTANCE AND BEARING FROM AN IRON CORNER FENCE POST SET IN CONCRETE."..."FOUND 1/2" IRON BAR

S75W 71.77' NAIL IN SE FACE 26" MAPLE
 S62E 61.22' SET NAIL AND MDNR TAG NE FACE 10" MAPLE
 N80E 104.07' SET NAIL AND MDNR TAG S. FACE POWER POLE
 N25E 87.41' SET NAIL AND MDNR TAG W. FACE 24" WALNUT
 SOUTH 4.63' FOUND 1/2" IRON BAR AT SOUTHWEST CORNER OF SECTION 19, T4N-R9W
 EAST 5' CENTERLINE ROBINSON (SIC) ROAD TO NORTH

5. AS ASSIGNED BY BARRY COUNTY REMONUMENTATION IN ADVANCE OF ANTICIPATED CONSTRUCTION, WITNESSED BY ROBERT JONKER P.S. #21572, MAY 8, 1993. "FOUND 1/2" REROD 5.5' NORTH OF C/L STATE ROAD

FOUND NAIL AND TAG ON WEST SIDE OF 30" WALNUT N25°E 87.44'
 FOUND NAIL IN SE SIDE OF A 30" MAPLE S68°W 71.80'
 FOUND NAIL AND TAG IN SOUTH SIDE OF POWER POLE N85°E 104.09'
 SW COR OF SEC 19-4-9 IRVING TOWNSHIP SOUTH 4.62'
 SET NAIL IN NW SIDE OF 16" MAPLE N32°E 72.78'

PART "B" (CONTINUED)

MR. ROBERTSON REPORTED THAT THE IRON FENCE POST, REFERENCED BY BILOW (NOW REMOVED IN THE COURSE OF ROAD CONSTRUCTION) WAS A NEWER POST, THAT THE OLDER FENCE POST WHICH WAS PRESENT AT THE TIME THE ROAD COMMISSION WITNESS TREES WERE PRESENT, WAS ABOUT 5 FEET FURTHER EAST. THIS MADE SENSE WITH THE OCCUPATION LINE SOUTH AND THE CENTERLINE OF ROBERTSON ROAD NORTH. WE THEN EXCAVATED 5 FEET FURTHER EAST AND RECOVERED BOTH THE CLOSING CORNER AND THE STANDARD CORNER MONUMENTS AS RECITED BY BOWEN (1876). THERE IS NO RECORD OF WHO SET THE IRON RECORDED BY BILOW AND REFERENCED BY JONKER, BUT IT CAN BE REASONABLY INFERRED FROM THE ABOVE INFORMATION THAT IT WAS SET IN REFERENCE TO THE WRONG IRON FENCE POST. FOUND STONE AND NUMEROUS PIECES OF WHITE AND RED BRICK. REMOVED STONE AND BRICK, REPLACED WITH STANDARD 3/4" X 24" REMON BAR AND CAP APPROXIMATELY 3 FEET BELOW ROAD GRADE. WITNESSES TO REMON IRON 3± FEET BELOW GRADE (INTENDED TO BE TEMPORARY UNTIL INSTALLATION OF MONUMENT BOX AND MONUMENT AT FINAL GRADE) MAY 28, 1994, MAPLE NNE 83.60', MAPLE WNW 80.15', GATE POST SOUTH 40.57'

ON JUNE 10, 1994, DON WOLF CALLED TO REPORT THAT THE BASE COURSE OF BITUMINOUS HAD BEEN PLACED. HE REQUESTED THAT WE RETURN TO PAINT THE LOCATION FOR THE MONUMENT BOXES TO BE PLACED BY THE ROAD COMMISSION IN ADVANCE OF THE FINAL SURFACE COARSE OF BITUMINOUS. THIS WAS DONE JUNE 13, 1994.

PART "C" (CONTINUED)

SURVEY &
 REMONUMENTATION
 AUG 31 1994
 COMMISSION

